



**ADDENDUM NO. 1
RFP # 20-0061**

Date: June 16, 2020
To: All Interested Parties
From: Grady Garrow, CPPB, CTCM, CTCD
Buyer
Re: **RFP No. 20-0061 Lake Houston Pump Station Screen Channel Rehabilitation**

The following additions, deletions, changes or clarifications to RFP No. 20-0061 are hereby made a part of the originally issued documents for the above referenced project as fully and as completely as though the same were included therein.

Drawings

- **Delete Note 1 on Sheet C-1 and replace with the following:**

“Contractor may use existing crane for work, refer to Specification Sections 01 11 13 and 01 14 19 for requirements.”

- **Add the following to Note 8 on Sheet C-1:**

“Channels to be installed so that the minimum horizontal distance between channel screen slots in each bay is 13’-11.5”. Contractor to prepare concrete surface as required to provide required distance.”

Specifications

- **Add the following to Specification Section 01 11 13 – Work Covered by Contract Documents Section 1.7.A.2**

“c. Contractor shall provide any additional rigging and hoisting components required to move, transfer, remove and install screens, channels, gratings, support beams and other components to be installed under this Contract. All

rigging and hoisting components and personnel shall follow current OSHA guidelines. Contractor shall provide certification to Owner that all hoisting equipment has been inspected and is certified.

- d. Contractor shall provide proof of a Certified Rigger Level II certification for each employee who will be planning and conducting the work associated with crane usage. NCCCO (National Commission for the Certification of Crane Operators) or equivalent accredited certification.”

- Add the following to Specification Section 01 11 13 – Work Covered by Contract Documents Section 1.9.A

“See Section 01 14 19-1.5.D for crane operation requirements.”

- Add the following to Specification Section 01 14 19 – Use of Premises Section 1.9

“J. Contractor shall provide appropriate safety provisions for fall protection when grating is removed during the work. Contractor to provide details in the Safety Plan submittal showing type(s), location and duration of fall protection system. Coordinate with pump station operator on removing grating in front of control room access doors, Contractor to provide safe access to control room in the event access is needed by pump station operator.”

- Add the following to Specification Section 01 14 19 – Use of Premises Section 1.3

“E. Operator crane certification(s).”

- Add the following to Specification Section 01 14 19 – Use of Premises Section 1.17.C

“Welding inside the pump station building is only permitted on the lower level. Contractor shall provide proper ventilation per OSHA guidelines for welding activities and air concentration monitoring.”

- Delete Specification Section 01 14 19 – Use of Premises Section 1.5.D and replace with the following:

“D. Contractor may use overhead crane located in the pump station for execution of work.

1. The crane is a Reading (Model TRE-DG-HG) 25-ton overhead crane which takes 2-3 people to operate. (See pictures)
2. Contractor shall provide proof of a Certified Rigger Level II certification for each employee who will be planning and conducting the work associated with crane usage. NCCCO (National Commission for the Certification of Crane Operators) or equivalent accredited certification.
3. Prior to operating crane, all personnel that will be involved in operating the crane will be required to attend a 1 day safety/operation training workshop at the pump station given by SJRA staff.

4. Training shall include:

- a. Site specific crane training with SJRA staff and Contractor**
- b. Handling and maneuvering practice drills to lay out a plan conducive to efficient and safe operations during the course of the project**
- c. Acknowledgment of training to be signed by all parties after participation.**
- d. Any Contractor's staff member joining at a later date will need to undergo the training referenced above, even if project work must be stopped so that training can occur."**

- Add the following to Specification Section 01 74 19 – Construction Waste Management and Disposal Section 3.1.B.**

“All metal grating removed shall remain the property of Owner, Contractor to coordinate with Owner on storage location of grating.”

All provisions which are not so amended or supplemented remain in full force and effect.

Please acknowledge receipt of this addendum with signature and date and return with completed Proposal/Quotation. Failure to do so may cause your Proposal to be considered non-responsive.

Receipt of this Addendum No. 1 is hereby acknowledged

Authorized Signature

Date

Company Name



