




The Woodlands

10-Year Project Plan

2026 – 2035





The Woodlands
10-Year Project Plan
FY 2026 – FY 2035

Date: 07/08/2025

CONTENTS

The Woodlands Executive Summary.....	1
The Woodlands Project Location Maps	3
The Woodlands Summary Sheets	5
Individual Project Sheets.....	7

**The Woodlands Division
10-Year Project Plan
Executive Summary
FY 2026 – FY 2035 Projects**

Introduction

The purpose of The Woodlands Division 10-Year Project Plan for Fiscal Years (FY) 2026 through 2035 is to identify potential projects and associated funding requirements and sources to appropriately maintain and manage the SJRA Woodlands Division’s extensive wholesale water supply and wastewater conveyance, and treatment assets; to continue to provide efficient and reliable services which is compliant to all state and federal regulations for the 11 Municipal Utility Districts (MUDs) in The Woodlands, Texas.

The Project Plan includes projects resulting from the Wastewater Strategic Plan, including a new Water Reclamation Facility No. 1, optimization of the conveyance system to Water Reclamation Facility No. 1, and associated land acquisition. In addition, projects to replace all asbestos cement water lines in The Woodlands are included. The AC Water Line Condition Based Assessment will confirm the timing and scope of these projects.

Key Focus Areas:


- New Water Reclamation Facility No. 1 and Optimized Conveyance System.
- Replacement of Aging Asbestos Cement Water Lines (235,000 LF)
- Construction of new Elevated Storage Tank
- Renewal of Aging Water Wells (26)
- Renewal of Elevated Water Storage Tanks (5)
- Renewal or Replacement of Aging Gravity Sanitary Sewers, Lift Stations, and Force Mains (37,000 LF)
- Renewal or Replacement of Aging Wastewater Treatment Plant Components
- Lift Station No. 24 site improvements for flood resiliency



Total Projected Costs (All Projects)		Funding Sources (10 – Year Period)	
Estimated Expenditures Thru End of FY2025	\$8,955,292	R&R Fund Water	\$44,774,513
FY 2026	\$40,847,280	R&R Fund Wastewater	\$40,047,291
FY 2027	\$59,236,800	2017 Bond Financed - Wastewater	\$27,843,719
FY 2028	\$102,361,900	New Bond Financed – Water	\$233,138,000
FY 2029 – FY 2035	\$517,775,000	New Bond Financed - Wastewater	\$381,547,749
		Federal Funds – Wastewater	\$1,825,000
		Total	\$729,176,272
Total	\$729,176,272	Total	\$729,176,272

**The Woodlands Division
10-Year Project Plan
Executive Summary
FY 2026 – FY 2035 Projects**

Risk Management

The Project Plan has been prepared utilizing condition, expected service life and available funding. Projects have been prioritized based on funding and renewal of some assets which may have been delayed past their recommended renewal service life timeline.





The Woodlands Project Summary - Water


The Woodlands
FY 2026 - FY 2035 Projects

PAGE NO.	PROJECT ID	PROJECT NAME	ESTIMATED EXPENDITURES THROUGH END OF FY 2025	2026 ESTIMATE	2027 ESTIMATE	2028 ESTIMATE	2029 ESTIMATE	2030 ESTIMATE	2031 ESTIMATE	2032 ESTIMATE	2033 ESTIMATE	2034 ESTIMATE	2035 ESTIMATE	TOTAL
7	WATCEA	Town Center Water Line Easements	\$ 242,424	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 242,424
8	WAEST6	Elevated Storage Tank No. 6	\$ 891,687	\$ 7,391,000	\$ 3,125,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 11,407,687
9	WA21WL	Town Center Water Line Replacement	\$ 647,649	\$ 1,470,980	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,118,629
10	WXWDWS	Digital Water System	\$ 613,773	\$ 350,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 963,773
11	WA25WR	Water Well No. 3 and 13 Rehabilitation	\$ -	\$ 1,125,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,125,000
12	WA26WR	Water Well Nos. 7, 15 and 30 Rehabilitation	\$ -	\$ 80,000	\$ 1,738,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,818,000
13	WAET5R	Elevated Storage Tank No. 5 Rehabilitation	\$ -	\$ -	\$ 237,000	\$ 1,013,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,250,000
14	WA27WR	Water Well Nos. 19 and 27 Rehabilitation	\$ -	\$ -	\$ 352,000	\$ 1,044,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,396,000
15	WAET7R	Elevated Storage Tank No. 7 Rehabilitation	\$ -	\$ -	\$ -	\$ 516,000	\$ 497,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,013,000
16	WA28WR	Water Well Nos. 8, 20 and 29 Rehabilitation	\$ -	\$ -	\$ -	\$ 1,142,000	\$ 994,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,136,000
17	WA29WR	Water Well Nos. 10, 16 and 35 Rehabilitation	\$ -	\$ -	\$ -	\$ -	\$ 709,000	\$ 1,424,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,133,000
18	WAET3R	Elevated Storage Tank No. 3 Rehabilitation	\$ -	\$ -	\$ -	\$ -	\$ 280,000	\$ 1,196,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,476,000
19	WA30WR	Water Well Nos. 18 and 36 Rehabilitation	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 369,000	\$ 815,000	\$ -	\$ -	\$ -	\$ -	\$ 1,184,000
20	WAET4R	Elevated Storage Tank No. 4 Rehabilitation	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 282,000	\$ 967,000	\$ -	\$ -	\$ -	\$ -	\$ 1,249,000
21	WA1WGN	Water Well Site Generator - Project 1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 162,000	\$ 1,164,000	\$ 388,000	\$ -	\$ -	\$ -	\$ 1,714,000
22	WA31WR	Water Well Nos. 9 and 14 Rehabilitation	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 567,000	\$ 1,175,000	\$ -	\$ -	\$ -	\$ 1,742,000
23	WA123A	Abandon Water Well Nos. 1 and 6	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 139,000	\$ 466,000	\$ -	\$ -	\$ -	\$ 605,000
24	WA32WR	Water Well Nos. 21, 23 and 38 Rehabilitation	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 675,000	\$ 933,000	\$ -	\$ -	\$ 1,608,000
25	WA2WGN	Water Well Site Generator - Project 2	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 176,000	\$ 502,000	\$ 517,000	\$ -	\$ 1,195,000
26	WA33WR	Water Well Nos. 24 and 37 Rehabilitation	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 411,000	\$ 1,069,000	\$ -	\$ 1,480,000
27	WAET2R	Elevated Storage Tank No. 2 Rehabilitation	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 387,000	\$ 1,326,000	\$ -	\$ 1,713,000
28	WAET1R	Elevated Storage Tank No. 1 Rehabilitation	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 324,000	\$ 1,664,000	\$ 1,988,000
29	WA3WGN	Water Well Site Generator - Project 3	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 478,000	\$ 1,060,000	\$ 1,538,000
30	WA34WR	Water Well Nos. 12 and 28 Rehabilitation	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 415,000	\$ 918,000	\$ 1,333,000
31	WA35WR	Water Well Nos. 17 and 39 Rehabilitation	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 346,000	\$ 346,000
		TOTAL WATER R&R FUNDS	\$ 2,395,533	\$ 10,416,980	\$ 5,452,000	\$ 3,715,000	\$ 2,480,000	\$ 3,433,000	\$ 3,513,000	\$ 2,553,000	\$ 2,699,000	\$ 4,129,000	\$ 3,988,000	\$ 44,774,513
32	WA21WL	Town Center Water Line Replacement	\$ -	\$ -	\$ 10,938,000	\$ 6,357,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 17,295,000
33	WA23WL	N. Town Center and S. Grogans Mill Road Water Line Replacement	\$ -	\$ -	\$ 3,409,000	\$ 5,399,000	\$ 14,091,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 22,899,000
34	WA24WL	Panther Creek Area Water Line Replacement	\$ -	\$ -	\$ 3,693,000	\$ 8,490,000	\$ 12,516,000	\$ 6,446,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 31,145,000
35	WA2GT1	Water Plant No. 2 Ground Storage Tank No. 1 Replacement	\$ -	\$ -	\$ -	\$ -	\$ 932,000	\$ 4,749,000	\$ 543,000	\$ -	\$ -	\$ -	\$ -	\$ 6,224,000
36	WA25WL	Conference/Resort Area Water Line Replacement	\$ -	\$ -	\$ -	\$ -	\$ 2,731,000	\$ 7,619,000	\$ 6,684,000	\$ -	\$ -	\$ -	\$ -	\$ 17,034,000
37	WA26WL	Sawmill Road and Grogans Point Drive Water Line Replacement	\$ -	\$ -	\$ -	\$ -	\$ 2,016,000	\$ 8,246,000	\$ 6,596,000	\$ -	\$ -	\$ -	\$ -	\$ 16,858,000
38	WA27WL	Millbend Water Line Replacement	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,518,000	\$ 6,971,000	\$ 11,920,000	\$ -	\$ -	\$ -	\$ 21,409,000
39	WA28WL	West Lake Area Water Line Replacement	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,431,000	\$ 7,485,000	\$ 8,912,000	\$ -	\$ -	\$ -	\$ 18,828,000
40	WAWW40	Water Well No. 40	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,575,000	\$ 2,757,000	\$ 5,131,000	\$ 2,462,000	\$ -	\$ -	\$ 11,925,000
41	WA29WL	West Panther Creek Area Water Line Replacement	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,656,000	\$ 9,581,000	\$ 8,116,000	\$ 20,353,000
42	WA30WL	South Panther Creek Area Water Line Replacement	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,442,000	\$ 9,539,000	\$ 7,918,000	\$ 19,899,000
43	WA31WL	Trade Center Area Water Line Replacement	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,069,000	\$ 5,747,000	\$ 4,751,000	\$ 12,567,000
44	WA32WL	Cochran's Crossing Area Water Line Replacement	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 3,704,000	\$ 8,105,000	\$ 11,809,000
45	WAWPWL	Woodlands Parkway Water Line Replacement	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,499,000	\$ 2,394,000	\$ 4,893,000
		TOTAL WATER FUTURE BOND FUNDS / UNFUNDED	\$ -	\$ -	\$ 18,040,000	\$ 20,246,000	\$ 32,286,000	\$ 33,584,000	\$ 31,036,000	\$ 25,963,000	\$ 9,629,000	\$ 31,070,000	\$ 31,284,000	\$ 233,138,000
		TOTAL SJRA WATER PROJECTS	\$ 2,395,533	\$ 10,416,980	\$ 23,492,000	\$ 23,961,000	\$ 34,766,000	\$ 37,017,000	\$ 34,549,000	\$ 28,516,000	\$ 12,328,000	\$ 35,199,000	\$ 35,272,000	\$ 277,912,513


The Woodlands Project Summary - Wastewater

The Woodlands
FY 2026 - FY 2035 Projects



PAGE NO.	PROJECT ID	PROJECT NAME	ESTIMATED EXPENDITURES THROUGH END OF FY 2025	2026 ESTIMATE	2027 ESTIMATE	2028 ESTIMATE	2029 ESTIMATE	2030 ESTIMATE	2031 ESTIMATE	2032 ESTIMATE	2033 ESTIMATE	2034 ESTIMATE	2035 ESTIMATE	TOTAL
46	WW21LS	Lift Station Rehabilitation	\$ 700,000	\$ 100,000	\$ 100,000	\$ 125,000	\$ 125,000	\$ 150,000	\$ 150,000	\$ 150,000	\$ 150,000	\$ 150,000	\$ 150,000	\$ 2,050,000
47	WW21GR	South Shore Gravity Main Rehabilitation	\$ 263,888	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 263,888
48	WWF1OA	Wastewater Owner's Advisor	\$ 834,096	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 834,096
49	WWLS1B	Lift Station No. 1 Gravity Main Bypass and Decommissioning	\$ 207,711	\$ 180,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 387,711
50	WWP2GC	WWTF No. 2 Grit Classifier Improvements	\$ 97,000	\$ 1,088,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,185,000
51	WW02FR	WWTF No. 2 Tertiary Filter Improvements (2nd and 3rd Filter)	\$ 435,327	\$ 92,000	\$ 8,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 535,327
52	WWF1LA	Wastewater System Land Acquisition	\$ 260,000	\$ 4,770,000	\$ 4,770,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 9,800,000
53	WWFM21	Lift Station No. 21 Force Main Renewal	\$ -	\$ 94,000	\$ 531,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 625,000
54	WWLS24	Lift Station 24 Improvements	\$ -	\$ 284,300	\$ 323,700	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 608,000
		Federal Funds	\$ -	\$ -	\$ 812,100	\$ 1,012,900	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,825,000
55	WWP3BS	Wastewater Treatment Facility No. 3 Bar Screen Replacement	\$ -	\$ -	\$ 220,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 220,000
56	WW13FM	Lift Station No. 13 Force Main Renewal	\$ -	\$ -	\$ 166,000	\$ 937,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,103,000
57	WW25CR	WWTF No. 2 Belt Press and Conveyor Replacement	\$ -	\$ -	\$ 733,000	\$ 2,233,000	\$ 3,564,000	\$ 1,836,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 8,366,000
58	WW22FM	Forcemain Renewal	\$ 86,269	\$ -	\$ -	\$ -	\$ 176,000	\$ 181,000	\$ 187,000	\$ 192,000	\$ 197,000	\$ 204,000	\$ 209,000	\$ 1,432,269
59	WW02CR	WWTF No. 2 Clarifier Rehabilitation	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 163,000	\$ 1,848,000	\$ -	\$ -	\$ -	\$ 2,011,000
60	WWP2BC	WWTF No. 2 Basin Coating	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 160,000	\$ 1,977,000	\$ 1,866,000	\$ -	\$ -	\$ 4,003,000
61	WWP2BR	WWTF No. 2 Blower Replacement	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 581,000	\$ 2,724,000	\$ 1,922,000	\$ -	\$ 5,227,000
62	WW03CR	WWTF No. 3 Clarifier Rehabilitation	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 85,000	\$ 961,000	\$ 1,046,000
63	WWP3BR	WWTF No. 3 Blower Replacement	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 350,000	\$ 350,000
		TOTAL R&R FUNDS	\$ 2,884,291	\$ 6,608,300	\$ 6,851,700	\$ 3,295,000	\$ 3,865,000	\$ 2,167,000	\$ 660,000	\$ 4,748,000	\$ 4,937,000	\$ 2,361,000	\$ 1,670,000	\$ 40,047,291
		TOTAL FEDERAL FUNDS	\$ -	\$ -	\$ 812,100	\$ 1,012,900	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,825,000
64	WWF1OA	Wastewater Owner's Advisor	\$ -	\$ 1,810,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,162,000	\$ -	\$ -	\$ -	\$ 14,162,000
65	WWF1NP	Water Reclamation Facility No. 1	\$ 1,787,286	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,787,286
		Water Reclamation Facility No. 1	\$ -	\$ 4,620,000	\$ 14,275,000	\$ 55,369,000	\$ 51,255,000	\$ 51,123,000	\$ 50,994,000	\$ 51,123,000	\$ -	\$ -	\$ -	\$ 278,759,000
66	WW02FR	WWTF No. 2 Tertiary Filter Improvements (2nd and 3rd Filter)	\$ 500,000	\$ 4,492,000	\$ 374,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 5,366,000
67	WWWWCO	Wastewater Conveyance Optimization	\$ 747,749	\$ 946,000	\$ 2,306,251	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 4,000,000
		Wastewater Conveyance Optimization	\$ -	\$ -	\$ 3,936,749	\$ 13,188,000	\$ 13,716,000	\$ 10,787,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 41,627,749
68	WW21GR	South Shore Gravity Main Rehabilitation	\$ 640,433	\$ 7,954,000	\$ 4,096,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 12,690,433
69	WWLS1B	Lift Station No. 1 Gravity Main Bypass and Decommissioning	\$ -	\$ 4,000,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 4,000,000
70	WW23GR	Gravity Main Rehabilitation - Hughes Landing and East Shore	\$ -	\$ -	\$ 1,055,000	\$ 2,700,000	\$ 5,844,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 9,599,000
71	WW25GR	Gravity Main Rehabilitation - North Bear Branch	\$ -	\$ -	\$ -	\$ 798,000	\$ 1,948,000	\$ 3,997,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 6,743,000
72	WW27GR	Gravity Main Rehabilitation - Upper Panther Branch	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,216,000	\$ 3,243,000	\$ 7,097,000	\$ -	\$ -	\$ -	\$ 11,556,000
73	WW31GR	Gravity Main Rehabilitation - West of Lake Woodlands	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,208,000	\$ 3,157,000	\$ 6,843,000	\$ -	\$ 11,208,000
74	WW32GR	Gravity Main Rehabilitation - East of Lake Woodlands	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 894,000	\$ 2,290,000	\$ 4,709,000	\$ -	\$ 7,893,000
		TOTAL 2017 BOND FUNDS	\$ 3,675,468	\$ 17,392,000	\$ 6,776,251	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 27,843,719
		TOTAL WASTEWATER FUTURE BOND FUNDS / UNFUNDED	\$ -	\$ 6,430,000	\$ 21,304,749	\$ 74,093,000	\$ 74,801,000	\$ 69,161,000	\$ 56,275,000	\$ 61,590,000	\$ 4,051,000	\$ 9,133,000	\$ 4,709,000	\$ 381,547,749
		TOTAL SJRA WASTEWATER PROJECTS	\$ 6,559,759	\$ 30,430,300	\$ 35,744,800	\$ 78,400,900	\$ 78,666,000	\$ 71,328,000	\$ 56,935,000	\$ 66,338,000	\$ 8,988,000	\$ 11,494,000	\$ 6,379,000	\$ 451,263,759
		TOTAL SJRA WATER AND WASTEWATER PROJECTS	\$ 8,955,292	\$ 41,056,204	\$ 59,236,800	\$ 102,361,900	\$ 113,432,000	\$ 108,345,000	\$ 91,484,000	\$ 94,854,000	\$ 21,316,000	\$ 46,693,000	\$ 41,651,000	\$ 729,385,196

PROJECT NAME				PROJECT ID	FISCAL YEAR			DIVISION				
Town Center Water Line Easements				WATCEA	2024-TBD			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE						
<p>This project was identified for the need to aquire additional easements necessary for the replacement of approximately 14,200 LF of asbestos cement (AC) water lines in the Town Center area. However, this project is currently on-hold pending the completion and results of the AC Water Line Condition Based Assessment project, which could re-prioritize the scope and schedule of the line replacements.</p> <p>For its water and sewer utilities, SJRA obtains permanent easements in both public and private properties and rights-of-way in order to guarantee the ability to install, operate, maintain, and if necessary remove its utilities. For this project, it has been found that the existing water line does not in all cases reside in an easement. Also, there are locations where the water line will be offset, particularly where crossing intersections, where new easements will be required. For this project, approximately 30 new permanent easements are required.</p> <p>In addition, to install the new line, there are locations where pits and laydown area for the water line required outside the area where permanent easements are to located. These locations require a temporary construction easement (TCE). There will be the need for approximately 20 TCEs for this project.</p> <p>A land acquisition team will be utilized to perform services to acquire these easements, both permanent and temporary. This team is comprised of a project manager/coordinator, legal counsel, a property aquisition specialist, and an abstractor/title researcher. This team will be responsible for identifying property ownership and verifying boundaries, coordinating and providing offers to property owners, and drafting and executing easement documents.</p>												
PROJECT SCHEDULE				DELIVERY	FUNDING							
Initiate Cons. Selection:		Completed		<input type="checkbox"/> CSP	<input type="checkbox"/> O&M							
PSA/WO Issued:		FY 2024 - Q1		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS							
Final Easement Documents		TBD		<input checked="" type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R							
Complete Easement Acquisition		TBD		<input checked="" type="checkbox"/> OTHER Professional Services and Legal Engagement	<input type="checkbox"/> GRANTS <input type="checkbox"/> OTHER Excess Funds							
BUDGET	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Engineering/Design	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
CPS, CM&I, and CMT	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Land Acquisition Team	\$ 242,424	\$ 242,424	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Property Cost	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total	\$ 242,424	\$ 242,424	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -

*Budget includes 30% contingency, and 3% inflation per year.


PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION					
Elevated Storage Tank No. 6				WAEST6		2024-2027			The Woodlands					
PROJECT DESCRIPTION				PROJECT MAP/PICTURE										
<p>SJRA received a TCEQ Notice of Violation on January 2017 indicating the water system contained insufficient elevated water storage for the number of connections in the system. SJRA was able to receive a temporary variance, but additional elevated storage capacity is required to address future demand needs. Elevated Storage Tanks (ESTs) provide pressure stabilization in the water distribution system, reducing the need for water plant booster pumps to operate constantly to maintain system pressure. ESTs also provide additional water storage in the event of a nearby fire event.</p> <p>Elevated Storage Tank No. 6 is proposed as an elevated storage tank (EST) to be constructed at the corner of Research Forest Drive and Egypt Lane, which is in the Upper Pressure Plane of the Woodlands Division water system. Placing the EST in the Upper Pressure Plane allows for pressure maintenance capability in all three pressure planes due to the ability for water transfer to occur from an upper to a lower pressure plane. It is planned that the new EST will be built on land SJRA previously acquired during master planning efforts in the past.</p> <p>The EST is proposed to have a 1 million gallon capacity based upon results of recent system modeling efforts and analysis of system operations. The elevated storage tank piping will connect to an existing 16-inch water line in the area. An access driveway will need to be constructed to access the site from Research Forest Drive. A forest buffer will be preserved around the site.</p>														
PROJECT SCHEDULE				DELIVERY	FUNDING									
Initiate Cons. Selection:		Completed		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:		Completed		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS									
Final Proposal Docs:		FY 2026 - Q1		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R									
Proposals/Bids Received:		FY 2026 - Q1		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		FY 2026 - Q2			<input type="checkbox"/> OTHER									
Substantial Completion:		FY 2027 - Q3												
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035		
Planning/Permitting/PER	\$ 581,687	\$ 581,687	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Engineering/Design	\$ 410,000	\$ 310,000	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Construction	\$ 9,469,000	\$ -	\$ 6,628,000	\$ 2,841,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
CPS, CM&I, and CMT	\$ 947,000	\$ -	\$ 663,000	\$ 284,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Total	\$ 11,407,687	\$ 891,687	\$ 7,391,000	\$ 3,125,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		

*Budget includes 30% contingency, and 3% inflation per year.



PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
Town Center Water Line Replacement				WA21WL		2021-TBD			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>This project is part of a phased asset management approach to continuously replace water lines that are beyond their service life, have had a number of repairs, and based on a 2024-2025 condition based assessment of the AC water lines in The Woodlands that is underway. The current plan is to replace all asbestos cement (AC) water lines within the next 10-15 years. The AC lines will be replaced with PVC or HDPE lines. The results of the assessment will be presented to The Woodlands MUDs to determine a path forward for AC water line replacement prioritization. This scope and schedule of the projects in this project plan could be adjusted based upon the results of the assessment, and would be reflected in future project plans. The existing distribution system contains approximately 48 miles of asbestos cement (AC) lines. Approximately 90% of all these water lines are more than 40 years old. Historically, SJRA has experienced on average 9 failures per year, and is trending upward.</p> <p>Approximately 14,000 linear feet (2.7 miles) of 12-inch AC water mains in the Grogan's Mill and Metro Center areas along Six Pines Drive between North Millbend Drive and Timberloch Place, along Lake Woodlands Drive from Hughes Landing Blvd to Pinecroft Drive, and along Grogan's Mill Road from Research Forest Drive to Woodlands Parkway were identified for this project scope. Costs are based on a Engineers Opinion of Construction Cost during the Final Design phase of this project from early 2023, with inflation and contingency added. Also, easement (land) acquisition will be required for adjusting position of lines and construction access with budget based upon existing cost estimates for similar areas (see WATCEA). Based on the outcome of the AC Water Line Condition Based Assessment, the timing and scope of this replacement could be adjusted. The preliminary and final design phases were funded by R&R funds.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:	Completed	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M										
PSA/WO Issued:	Completed	<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS										
Final Proposal Docs:	TBD	<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R										
Proposals/Bids Received:	TBD	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS										
Constr. Contract to Board:	TBD		<input type="checkbox"/> OTHER										
Substantial Completion:	TBD												
BUDGET**	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER*	\$ 299,315	\$ 299,315	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design*	\$ 1,819,314	\$ 348,334	\$ 1,470,980	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 15,723,000	\$ -	\$ -	\$ 9,944,000	\$ 5,779,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 1,572,000	\$ -	\$ -	\$ 994,000	\$ 578,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 19,413,629	\$ 647,649	\$ 1,470,980	\$ 10,938,000	\$ 6,357,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	

*In Previous funding, was R&R funded for design for \$647,649 total, and in 2026 an additional \$1,470,980 will be R&R funded for design.


**Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID	FISCAL YEAR	DIVISION													
Digital Water System				WXWDWS	2022-2026	The Woodlands													
PROJECT DESCRIPTION				PROJECT MAP/PICTURE															
<p>To improve the efficiency of asset renewal planning and operational data review and reporting, the SJRA Woodlands Division has started development of an advanced infrastructure analytics platform (DWS). A DWS is generally defined as a combination of software, databases, and web applications to form an integrated system for organizing, processing and visualizing planning, operational and managing water-related data and decisions. The purpose of the DWS is to provide a nexus for SJRA's people, processes, and technology to intersect in an integrated system that will provide the architecture and technology for a "smarter" water system from planning through operations.</p> <p>Previously, dashboards have been developed for monitoring of wastewater operational process parameters utilizing SCADA data and the Woodlands Division asset register. These dashboards are directly linked to regularly updated source data.</p> <p>The last stage of development will entail the development of operational dashboards that assist in water quality projections, quicker identification of service outages due to water breaks, and water system wide water quality information. Part of the budget will allow for the purchase of the software required to integrate with SJRA's water modeling software, field SCADA data, and AMI data to allow for real-time and predictive analysis.</p>																			
				PROJECT SCHEDULE				DELIVERY	FUNDING										
				Initiate Cons. Selection:				FY 2022 - Q1	<input type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:				FY2022 - Q2	<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS													
Final Proposal Docs:				N/A	<input checked="" type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R													
Proposals/Bids Received:				N/A	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS													
Constr. Contract to Board:				N/A		<input type="checkbox"/> OTHER													
Substantial Completion:				FY 2026 - Q4															
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035							
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -							
Engineering/Design	\$ 963,773	\$ 613,773	\$ 350,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -							
Construction	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -							
CPS, CM&I, and CMT	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -							
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -							
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -							
Total	\$ 963,773	\$ 613,773	\$ 350,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -							


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION					
Water Well No. 3 and 13 Rehabilitation				WA25WR		2025-2026			The Woodlands					
PROJECT DESCRIPTION						PROJECT MAP/PICTURE								
<p>Water Well Nos. 3 and 13 are currently out-of-service due to a significant loss of pumping capability. Water Well Nos. 3 and 13 showed indications of significant production decline in March 2025 and June 2024 respectively and both were shut off soon once their production fell below 250 gpm (the well pumps are designed to produce 1,300 gpm and 1,500 gpm respectively). Due to the failure of the well pumps, both wells will be rehabilitated and their pumping equipment replaced.</p> <p>Rehabilitation will begin with an inspection of all well related equipment and a video of the well to identify what caused the well pump failure and to identify well rehabilitation needs. The project will include replacement of pump and well equipment; wire brushing the well screen section; and jetting out and removing fill material from the bottom of the well. Since the Water Well No. 3 pumping equipment will be replaced, the new well pump will be placed 50 feet lower per recommendations from the 2022 Water Well Master Plan developed by INTERA Incorporated. No increase in well capacity is planned.</p> <p>Water Well No. 3 - Jasper Aquifer; Design GPM: 1,300; Last Rehab: 2016; Current GPM: 0 Status: Out-of-Service (March 2025)</p> <p>Water Well No. 13 - Jasper Aquifer; Design GPM: 1,500; Last Rehab: 2013; Current GPM: 0 Status: Out-of-Service (June 2024)</p> <p>Costs are based on previous well rehabilitation projects of similar scope and pump lowering. Design and CM&I is being performed in-house.</p>														
PROJECT SCHEDULE				DELIVERY	FUNDING									
Initiate Cons. Selection:		N/A - In-House		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:		N/A - In-House		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS									
Final Proposal Docs:		FY 2025 - Q3		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R									
Proposals/Bids Received:		FY 2025 - Q4		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		FY 2025 - Q4			<input type="checkbox"/> OTHER									
Substantial Completion:		FY 2026 - Q4												
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035		
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Engineering/Design	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Construction	\$ 1,071,000	\$ -	\$ 1,071,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
CPS, CM&I, and CMT	\$ 54,000	\$ -	\$ 54,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Total	\$ 1,125,000	\$ -	\$ 1,125,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID	FISCAL YEAR			DIVISION							
Water Well Nos. 7, 15 and 30 Rehabilitation				WA26WR	2026-2027			The Woodlands							
PROJECT DESCRIPTION				PROJECT MAP/PICTURE											
<p>Water Well Nos. 7, 15 and 30 are currently out-of-service due to a significant loss of pumping capability. Water Well Nos. 7, 15 and 30 showed indications of significant production decline and mechanical issues in June 2024, March 2025 and January 2024 respectively. At that time, the pumping production fell below 250 gpm (the well pumps are designed to produce 1,500 GPM, 1,600 GPM and 800 GPM respectively) and was subsequently shut-off. Due to the failure of the well pumps, all three wells will be rehabilitated and their pumping equipment replaced.</p> <p>For all three wells, the pumping equipment will be removed and inspected, and the a video of the well will be performed to identify well rehabilitation needs. The project will include replacement of pump and well equipment; wire brushing the well screen section; and jetting out and removing fill material from the bottom of the well. Since the Water Well No. 7 pumping equipment will be replaced, the new well pump will be placed 50 feet lower per the recommendations of the master plan. No increase in well capacity is planned.</p> <p>Water Well No. 7 - Jasper Aquifer; Design GPM: 1,500; Last Rehab: 2010; Current GPM: 0 Status: Out-of-Service (June 2024)</p> <p>Water Well No. 15 - Jasper Aquifer; Design GPM: 1,600; Last Rehab: 2014; Current GPM: 0 Status: Out-of-Service (March 2025)</p> <p>Water Well No. 30 - Evangeline Aquifer; Design GPM: 800; Last Rehab: 2008; Current GPM: 0 Status: Out-of-Service (January 2024)</p> <p>Costs are based on previous well rehabilitation projects of similar scope, including pump lowering.</p>															
				PROJECT SCHEDULE			DELIVERY	FUNDING							
				Initiate Cons. Selection:		FY 2026 - Q1	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M							
				PSA/WO Issued:		FY 2026 - Q1	<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS							
				Final Proposal Docs:		FY 2026 - Q3	<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R							
Proposals/Bids Received:		FY 2026 - Q4	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS											
Constr. Contract to Board:		FY 2026 - Q4		<input type="checkbox"/> OTHER											
Substantial Completion:		FY 2027 - Q4													
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035			
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -			
Engineering/Design	\$ 80,000	\$ -	\$ 80,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -			
Construction	\$ 1,655,000	\$ -	\$ -	\$ 1,655,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -			
CPS, CM&I, and CMT	\$ 83,000	\$ -	\$ -	\$ 83,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -			
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -			
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -			
Total	\$ 1,818,000	\$ -	\$ 80,000	\$ 1,738,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -			


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR		DIVISION				
Elevated Storage Tank No. 5 Rehabilitation				WAET5R		2027-2028		The Woodlands				
PROJECT DESCRIPTION				PROJECT MAP/PICTURE								
<p>Elevated Storage Tank No. 5 is a 1,000,000 gallon tank and was constructed in 2000. Based on an engineering report completed in 2013, the exterior and interior coating systems were replaced in 2015. A follow-up inspection of the tank will be completed in FY2026 to identify the need and scope for any additional rehabilitation work. Anticipated rehabilitation of the tank includes recoating of the tank exterior and interior surfaces to continue to protect the structure from corrosion. Additionally, modifications will be identified and installed for the future installation of water re-circulation equipment.</p> <p>To protect the metal structure from corrosion and to extend the useful life of the tank, periodic protective coating system replacement is required. The epoxy interior coating systems are anticipated to meet their protective value in about 12-15 years and require system replacement in order to continue to provide adequate corrosion protection. The useful life of the fluoropolymer exterior coating is expected to be 10-12 years.</p> <p>Projected costs are based on previous work conducted on the six Woodlands Division elevated storage tanks and industry pricing received from a third-party consultant in 2023, adjusted for inflation.</p>												
PROJECT SCHEDULE				DELIVERY	FUNDING							
Initiate Cons. Selection:		FY 2027		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M							
PSA/WO Issued:		FY 2027		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS							
Final Proposal Docs:		FY 2027		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R							
Proposals/Bids Received:		FY 2027		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS							
Constr. Contract to Board:		FY 2027			<input type="checkbox"/> OTHER							
Substantial Completion:		FY 2028										
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035
Planning/Permitting/PER	\$ 94,000	\$ -	\$ -	\$ 94,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Engineering/Design	\$ 94,000	\$ -	\$ -	\$ 94,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction	\$ 966,000	\$ -	\$ -	\$ 45,000	\$ 921,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
CPS, CM&I, and CMT	\$ 96,000	\$ -	\$ -	\$ 4,000	\$ 92,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total	\$ 1,250,000	\$ -	\$ -	\$ 237,000	\$ 1,013,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -




*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
Water Well Nos. 19 and 27 Rehabilitation				WA27WR		2027-2028			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>Water Well Nos. 19 and 27 have been identified for this project to have well rehabilitation performed and pumping equipment replaced. INTERA Incorporated produced a Water Well Master Plan in 2022. Based this master plan schedule identified, Well Nos. 19 and 27 for water well rehabilitation and equipment replacement for FY2027-2028. For the two wells, the pumping equipment will be removed and inspected, and the a video of the well will be performed to identify well rehabilitation needs. The project will include replacement of pump and well equipment; wire brushing the well screen section; and jetting out and removing fill material from the bottom of the well. Since the Water Well Nos. 19 and 27 pumping equipment will be replaced, the new well pump will be placed 150 feet and 80 feet lower respectively per the recommendations of the master plan. The motor for Water Well No. 19 will need to be increased from 200 HP to 250 HP. No increase in well capacity is planned.</p> <p>Water Well No. 19 - Jasper Aquifer; Design GPM: 650; Last Rehab: 2009; Current GPM: 610 Status: In-Service</p> <p>Water Well No. 27 - Jasper Aquifer; Design GPM: 1,500; Last Rehab: 2011; Current GPM: 1,430 Status: In-Service</p> <p>Costs are based on previous well rehabilitation projects of similar scope, and pricing to lower the pump. SJRA will install a 250HP motor.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		FY 2027	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:		FY 2027	<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS									
Final Proposal Docs:		FY 2027	<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R									
Proposals/Bids Received:		FY 2027	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		FY 2027		<input type="checkbox"/> OTHER									
Substantial Completion:		FY 2028											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 62,000	\$ -	\$ -	\$ 62,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 1,270,000	\$ -	\$ -	\$ 276,000	\$ 994,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 64,000	\$ -	\$ -	\$ 14,000	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 1,396,000	\$ -	\$ -	\$ 352,000	\$ 1,044,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID	FISCAL YEAR	DIVISION								
Elevated Storage Tank No. 7 Rehabilitation				WAET7R	2028-2029	The Woodlands								
PROJECT DESCRIPTION					PROJECT MAP/PICTURE									
<p>Elevated Storage Tank No. 7 is a 500,000 gallon tank and was constructed in 1977. Based on an engineering report completed in 2013, the exterior and interior coating systems were replaced in 2016. A follow-up inspection of the tank will be completed in FY2026 to identify the need and scope for any additional rehabilitation work. Anticipated rehabilitation of the tank includes recoating of the tank exterior and interior surfaces for maintenance and to continue to protect the exterior and interior from corrosion. Additionally, modifications will be identified and installed for the future installation of water re-circulation equipment.</p> <p>To protect the metal structure from corrosion and to extend the useful life of the tank, periodic protective coating system replacement is required. The epoxy interior coating systems are anticipated to meet their protective value in about 12-15 years and require system replacement in order to continue to provide adequate corrosion protection. The useful life of the fluoropolymer exterior coating is expected to be 10-12 years.</p> <p>Projected costs are based on previous work conducted on the six Woodlands Division elevated storage tanks and industry pricing received from a third-party consultant in 2023, adjusted for inflation.</p>														
PROJECT SCHEDULE				DELIVERY	FUNDING									
Initiate Cons. Selection:		FY 2028		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:		FY 2028		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS									
Final Proposal Docs:		FY 2028		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R									
Proposals/Bids Received:		FY 2028		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		FY 2028			<input type="checkbox"/> OTHER									
Substantial Completion:		FY 2029												
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035		
Planning/Permitting/PER	\$ 77,000	\$ -	\$ -	\$ -	\$ 77,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Engineering/Design	\$ 77,000	\$ -	\$ -	\$ -	\$ 77,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Construction	\$ 781,000	\$ -	\$ -	\$ -	\$ 329,000	\$ 452,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
CPS, CM&I, and CMT	\$ 78,000	\$ -	\$ -	\$ -	\$ 33,000	\$ 45,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Total	\$ 1,013,000	\$ -	\$ -	\$ -	\$ 516,000	\$ 497,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID	FISCAL YEAR	DIVISION						
Water Well Nos. 8, 20 and 29 Rehabilitation				WA28WR	2028-2029	The Woodlands						
PROJECT DESCRIPTION					PROJECT MAP/PICTURE							
<p>Water Well Nos. 8, 20 and 29 have been identified for this project to have well rehabilitation performed and pumping equipment replaced. INTERA Incorporated produced a Water Well Master Plan in 2022. Based this master plan schedule identified, Well Nos. 8, 20 and 29 for water well rehabilitation and equipment replacement for FY2028-2029. For all three wells, the pumping equipment will be removed and inspected, and the a video of the well will be performed to identify well rehabilitation needs. The project will include replacement of pump and well equipment; wire brushing the well screen section; and jetting out and removing fill material from the bottom of the well. Since the Water Well No. 29 pumping equipment will be replaced, the new well pump will be placed 100 feet lower per the recommendations of the master plan. No increase in well capacity is planned.</p> <p>Water Well No. 8 - Evangeline Aquifer; Design GPM: 800; Last Rehab: 2010; Current GPM: 800 Status: In-Service</p> <p>Water Well No. 20 - Evangeline Aquifer; Design GPM: 1,100; Last Rehab: 2012; Current GPM: 1,090 Status: In-Service</p> <p>Water Well No. 29 - Jasper Aquifer; Design GPM: 2,000; Last Rehab: 2011; Current GPM: 2,000 Status: In-Service</p> <p>Costs are based on previous well rehabilitation projects of similar scope, including lowering the well pump.</p>												
												
												
					PROJECT SCHEDULE				DELIVERY	FUNDING		
Initiate Cons. Selection:		FY 2028		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M							
PSA/WO Issued:		FY 2028		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS							
Final Proposal Docs:		FY 2028		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R							
Proposals/Bids Received:		FY 2028		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS							
Constr. Contract to Board:		FY 2028			<input type="checkbox"/> OTHER							
Substantial Completion:		FY 2029										
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Engineering/Design	\$ 176,000	\$ -	\$ -	\$ -	\$ 176,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction	\$ 1,782,000	\$ -	\$ -	\$ -	\$ 878,000	\$ 904,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
CPS, CM&I, and CMT	\$ 178,000	\$ -	\$ -	\$ -	\$ 88,000	\$ 90,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total	\$ 2,136,000	\$ -	\$ -	\$ -	\$ 1,142,000	\$ 994,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
Water Well Nos. 10, 16 and 35 Rehabilitation				WA29WR		2029-2030			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>Water Well Nos. 10, 16 and 35 have been identified for this project to have well rehabilitation performed and pumping equipment replaced. INTERA Incorporated produced a Water Well Master Plan in 2022. Based this master plan schedule identified, Well Nos. 10, 16 and 35 for water well rehabilitation and equipment replacement for FY2029-2030. For all three wells, the pumping equipment will be removed and inspected, and the a video of the well will be performed to identify well rehabilitation needs. The project will include replacement of pump and well equipment; wire brushing the well screen section; and jetting out and removing fill material from the bottom of the well. Since the Water Well No. 35 pumping equipment will be replaced, the new well pump will be placed 100 feet lower per recommendations of the master plan. As a result, the motor on Water Well No. 35 will have to be increased from 400 HP to 450 HP. No increase in well capacity is planned.</p> <p>Water Well No. 10 - Evangeline Aquifer; Design GPM: 800; Last Rehab: 2012; Current GPM: 690 Status: In-Service</p> <p>Water Well No. 16 - Evangeline Aquifer; Design GPM: 1,000; Last Rehab: 2011; Current GPM: 1,060 Status: In-Service</p> <p>Water Well No. 35 - Jasper Aquifer; Design GPM: 1,700; Installed: 2011; Current GPM: 1,820</p> <p>Costs are based on previous well rehabilitation projects of similar scope, pump lowering and pricing to replace the well motors.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		FY 2029	<input checked="" type="checkbox"/> CSP	<input checked="" type="checkbox"/> O&M									
PSA/WO Issued:		FY 2029	<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS									
Final Proposal Docs:		FY 2029	<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R									
Proposals/Bids Received:		FY 2029	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		FY 2029		<input type="checkbox"/> OTHER									
Substantial Completion:		FY 2030											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 95,000	\$ -	\$ -	\$ -	\$ -	\$ 95,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 1,941,000	\$ -	\$ -	\$ -	\$ -	\$ 585,000	\$ 1,356,000	\$ -	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 97,000	\$ -	\$ -	\$ -	\$ -	\$ 29,000	\$ 68,000	\$ -	\$ -	\$ -	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 2,133,000	\$ -	\$ -	\$ -	\$ -	\$ 709,000	\$ 1,424,000	\$ -	\$ -	\$ -	\$ -	\$ -	


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR		DIVISION					
Elevated Storage Tank No. 3 Rehabilitation				WAET3R		2029-2030		The Woodlands					
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>Elevated Storage Tank No. 3 is a 750,000 gallon tank and was constructed in 1990. Based on an engineering report completed in 2013, the exterior and interior coating systems were replaced in 2017. A follow-up inspection of the tank will be completed in FY2026 to identify the need and scope for any additional rehabilitation work. Anticipated rehabilitation of the tank includes recoating of the tank exterior and interior surfaces for maintenance and to continue to protect the exterior and interior from corrosion. Additionally, modifications will be identified and installed for the future installation of water re-circulation equipment.</p> <p>To protect the metal structure from corrosion and to extend the useful life of the tank, periodic protective coating system replacement is required. The epoxy interior coating systems are anticipated to meet their protective value in about 12-15 years and require system replacement in order to continue to provide adequate corrosion protection. The useful life of the fluoropolymer exterior coating is expected to be 10-12 years.</p> <p>Projected costs are based on previous work conducted on the six Woodlands Division elevated storage tanks and industry pricing received from a third-party consultant in 2023, adjusted for inflation.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		FY 2029		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		FY 2029		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS								
Final Proposal Docs:		FY 2029		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R								
Proposals/Bids Received:		FY 2029		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		FY 2029			<input type="checkbox"/> OTHER								
Substantial Completion:		FY 2030											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 111,000	\$ -	\$ -	\$ -	\$ -	\$ 111,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 111,000	\$ -	\$ -	\$ -	\$ -	\$ 111,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 1,140,000	\$ -	\$ -	\$ -	\$ -	\$ 53,000	\$ 1,087,000	\$ -	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 114,000	\$ -	\$ -	\$ -	\$ -	\$ 5,000	\$ 109,000	\$ -	\$ -	\$ -	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 1,476,000	\$ -	\$ -	\$ -	\$ -	\$ 280,000	\$ 1,196,000	\$ -	\$ -	\$ -	\$ -	\$ -	



*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID	FISCAL YEAR	DIVISION							
Water Well Nos. 18 and 36 Rehabilitation				WA30WR	2030-2031	The Woodlands							
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>Water Well Nos. 18 and 36 have been identified for this project to have well rehabilitation performed and pumping equipment replaced. INTERA Incorporated produced a Water Well Master Plan in 2022. Based this master plan schedule identified, Well Nos. 18 and 36 for water well rehabilitation and equipment replacement for FY2030-2031. For the two wells, the pumping equipment will be removed and inspected, and the a video of the well will be performed to identify well rehabilitation needs. The project will include replacement of pump and well equipment; wire brushing the well screen section; and jetting out and removing fill material from the bottom of the well. No pump lowering or increase in well capacity is planned.</p> <p>Water Well No. 18 - Evangeline Aquifer; Design GPM: 900; Last Rehab: 2012; Current GPM: 910 Status: In-Service</p> <p>Water Well No. 36 - Evangeline Aquifer; Design GPM: 950; Installed: 2011; Current GPM: 1,010 Status: In-Service</p> <p>Costs are based on previous well rehabilitation projects of similar scope.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		FY 2030		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		FY 2030		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS								
Final Proposal Docs:		FY 2030		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R								
Proposals/Bids Received:		FY 2030		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		FY 2031			<input type="checkbox"/> OTHER								
Substantial Completion:		FY 2031											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 53,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 53,000	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 1,077,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 301,000	\$ 776,000	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 54,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 15,000	\$ 39,000	\$ -	\$ -	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 1,184,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 369,000	\$ 815,000	\$ -	\$ -	\$ -	\$ -	


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION					
Elevated Storage Tank No. 4 Rehabilitation				WAET4R		2030-2031			The Woodlands					
PROJECT DESCRIPTION						PROJECT MAP/PICTURE								
<p>Elevated Storage Tank No. 4 is a 750,000 gallon tank and was constructed in 1990. Based on an engineering report completed in 2013, the exterior and interior coating systems were replaced in 2017 per the engineer's recommendation. A follow-up inspection of the tank will be completed in FY2026 to identify the need and scope for any additional rehabilitation work. Anticipated rehabilitation of the tank includes recoating of the tank exterior and interior surfaces for maintenance and to continue to protect the exterior and interior from corrosion. Additionally, modifications will be identified and installed for the future installation of water re-circulation equipment.</p> <p>To protect the metal structure from corrosion and to extend the useful life of the tank, periodic protective coating system replacement is required. The epoxy interior coating systems are anticipated to meet their protective value in about 12-15 years and require system replacement in order to continue to provide adequate corrosion protection. The useful life of the fluoropolymer exterior coating is expected to be 10-12 years.</p> <p>Projected costs are based on previous work conducted on the six Woodlands Division elevated storage tanks and industry pricing received from a third-party consultant in 2023, adjusted for inflation.</p>														
PROJECT SCHEDULE				DELIVERY	FUNDING									
Initiate Cons. Selection:		FY 2030		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:		FY 2030		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS									
Final Proposal Docs:		FY 2030		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R									
Proposals/Bids Received:		FY 2030		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		FY 2030			<input type="checkbox"/> OTHER									
Substantial Completion:		FY 2031												
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035		
Planning/Permitting/PER	\$ 94,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 94,000	\$ -	\$ -	\$ -	\$ -	\$ -		
Engineering/Design	\$ 94,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 94,000	\$ -	\$ -	\$ -	\$ -	\$ -		
Construction	\$ 964,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 85,000	\$ 879,000	\$ -	\$ -	\$ -	\$ -		
CPS, CM&I, and CMT	\$ 97,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 9,000	\$ 88,000	\$ -	\$ -	\$ -	\$ -		
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Total	\$ 1,249,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 282,000	\$ 967,000	\$ -	\$ -	\$ -	\$ -		





*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
Water Well Site Generator - Project 1				WA1WGN		2030-2032			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>The San Jacinto River Authority (SJRA) Woodlands Division owns and operates thirty-seven (37) groundwater wells. The groundwater produced by these wells is conveyed to the five (5) water plants where it is mixed with surface water, chlorinated, and pumped into the distribution system.</p> <p>As surface water is considered a supplemental source, the Woodlands Division must have the ability to produce sufficient groundwater to provide the needs of The Woodlands if surface water is not available to comply with TCEQ regulations. Automated standby power is the solution during power outages.</p> <p>Backup power at off-site (non-water plant) well locations and wells at elevated storage tank sites (EST) is provided by natural gas auxiliary engines (except EST No. 5), which are connected to water wells via a right-angle gear connection. This right-angle gear connection is manually engaged during a power outage to operate only the well it is connected to. Most of the existing engines are over 30 years of age with several over 40 years of age. Due to the age of this equipment, parts are becoming scarce, and issues are taking longer to be repaired. SJRA Woodlands Division has implemented a program to replace existing auxiliary engines with natural gas or diesel generators (as the sites permit) at 12 sites comprising 23 wells. Replacing the existing auxiliary engines with generators allows for either water well on the site to be powered, generators to operate automatically in a power outage, and parts to be readily available.</p> <p>This project will install one generator well site, which has to be sized to run the largest well at the site. Costs were based on a previous installation costs at other SJRA facilities of the approximate generator size needed for running one 450 HP well motor which is 600 kW.</p>						 							
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:	FY 2030		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:	FY 2030		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS									
Final Proposal Docs:	FY 2030		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R									
Proposals/Bids Received:	FY 2030		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:	FY 2031			<input type="checkbox"/> OTHER									
Substantial Completion:	FY 2032												
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 65,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 65,000	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 130,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 97,000	\$ 33,000	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 1,381,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,028,000	\$ 353,000	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 138,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 103,000	\$ 35,000	\$ -	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 1,714,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 162,000	\$ 1,164,000	\$ 388,000	\$ -	\$ -	\$ -	


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION								
Water Well Nos. 9 and 14 Rehabilitation				WA31WR		2031-2032			The Woodlands								
PROJECT DESCRIPTION				PROJECT MAP/PICTURE													
<p>Water Well Nos. 9 and 14 have been identified for this project to have well rehabilitation performed and pumping equipment replaced. INTERA Incorporated produced a Water Well Master Plan in 2022. Based this master plan schedule identified, Well Nos. 9 and 14 for water well rehabilitation and equipment replacement for FY2031-2032. For the two wells, the pumping equipment will be removed and inspected, and the a video of the well will be performed to identify well rehabilitation needs. The project will include replacement of pump and well equipment; wire brushing the well screen section; and jetting out and removing fill material from the bottom of the well. Since the Water Well No. 9 pumping equipment will be replaced, the new well pump will be placed 100 feet lower per recommendations of the master plan. No increase in well capacity is planned.</p> <p>Water Well No. 9 - Jasper Aquifer; Design GPM: 1,500; Last Rehab: 2011; Current GPM: 1,100 Water Well No. 14 - Evangeline Aquifer; Design GPM: 700; Installed: 2008; Current GPM: 650</p> <p>Costs are based on previous well rehabilitation projects of similar scope, including lowering the pump.</p>																	
				PROJECT SCHEDULE				DELIVERY	FUNDING								
				Initiate Cons. Selection:		FY 2031		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		FY 2031		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS												
Final Proposal Docs:		FY 2031		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R												
Proposals/Bids Received:		FY 2031		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS												
Constr. Contract to Board:		FY 2031			<input type="checkbox"/> OTHER												
Substantial Completion:		FY 2032															
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035					
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -					
Engineering/Design	\$ 78,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 78,000	\$ -	\$ -	\$ -	\$ -					
Construction	\$ 1,585,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 466,000	\$ 1,119,000	\$ -	\$ -	\$ -					
CPS, CM&I, and CMT	\$ 79,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 23,000	\$ 56,000	\$ -	\$ -	\$ -					
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -					
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -					
Total	\$ 1,742,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 567,000	\$ 1,175,000	\$ -	\$ -	\$ -					


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
Abandon Water Well Nos. 1 and 6				WA123A		2032-2033			The Woodlands				
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>Water Well Nos. 1 and 6 were installed in 1974 and 1984, respectively. By 2030, these water wells will be near or over their useful service life of 50 years, and have already had operational and/or structural issues which prohibit or reduce their rehabilitation potential. Water Well Nos. 1 and 6 pump from the Evangeline Aquifer.</p> <p>Well No. 1 has a bent structural casing and is the lowest producing water well. The bent structural casing restricts any mechanical rehabilitation or lowering of the pump. After Well No. 1, Well No. 6 is the lowest producing water well, and any future rehabilitation will take significant electrical and backup power upgrades to replace deteriorated equipment. The budgeted costs are based upon a previous well abandonment and estimates from third-party consultants.</p> <div><div><u>Water Well No. 1</u> Design GPM: 450 Evangeline Aquifer Installed: 1973</div><div><u>Water Well No. 6</u> Design GPM: 600 Evangeline Aquifer Installed: 1984</div></div>				 									
				 									
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:				FY 2032	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M							
PSA/WO Issued:				FY 2032	<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS							
Final Proposal Docs:				FY 2032	<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R							
Proposals/Bids Received:				FY 2032	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS							
Constr. Contract to Board:				FY 2032		<input type="checkbox"/> OTHER							
Substantial Completion:				FY 2033									
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 49,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 49,000	\$ -	\$ -	\$ -	
Construction	\$ 506,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 82,000	\$ 424,000	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 8,000	\$ 42,000	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 605,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 139,000	\$ 466,000	\$ -	\$ -	


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
Water Well Nos. 21, 23 and 38 Rehabilitation				WA32WR		2032-2033			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>Water Well Nos. 21, 23 and 38 have been identified for this project to have well rehabilitation performed and pumping equipment replaced. INTERA Incorporated produced a Water Well Master Plan in 2022. Based this master plan schedule identified, Well Nos. 21, 23 and 38 for water well rehabilitation and equipment replacement for FY2032-2033. For all three wells, the pumping equipment will be removed and inspected, and the a video of the well will be performed to identify well rehabilitation needs. The project will include replacement of pump and well equipment; wire brushing the well screen section; and jetting out and removing fill material from the bottom of the well. Since the Water Well No. 21 pumping equipment will be replaced, the new well pump will be placed 50 feet lower per the recommendations of the master plan. No increase in well capacity is planned.</p> <p>Water Well No. 21 - Jasper Aquifer; Design GPM: 1,600; Last Rehab: 2014; Current GPM: 1,780 Status: In-Service</p> <p>Water Well No. 23 - Jasper Aquifer; Design GPM: 1,500; Last Rehab: 2021; Current GPM: 1,650 Status: In-Service</p> <p>Water Well No. 38 - Evangeline Aquifer; Design GPM: 900; Installed: 2006; Current GPM: 1,070 Status: In-Service</p> <p>Costs are based on previous well rehabilitation projects of similar scope and pricing to lower a well pump.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		FY 2032	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:		FY 2032	<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS									
Final Proposal Docs:		FY 2032	<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R									
Proposals/Bids Received:		FY 2032	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		FY 2032		<input type="checkbox"/> OTHER									
Substantial Completion:		FY 2033											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 132,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 132,000	\$ -	\$ -	\$ -	
Construction	\$ 1,342,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 494,000	\$ 848,000	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 134,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 49,000	\$ 85,000	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 1,608,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 675,000	\$ 933,000	\$ -	\$ -	


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
Water Well Site Generator - Project 2				WA2WGN		2032-2034			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>The San Jacinto River Authority (SJRA) Woodlands Division owns and operates thirty-seven (37) groundwater wells. The groundwater produced by these wells is conveyed to the five (5) water plants where it is mixed with surface water, chlorinated, and pumped into the distribution system.</p> <p>As surface water is considered a supplemental source, the Woodlands Division must have the ability to produce sufficient groundwater to provide the needs of The Woodlands if surface water is not available to comply with TCEQ regulations. Automated standby power is the solution during power outages.</p> <p>Backup power at off-site (non-water plant) well locations and wells at elevated storage tank sites (EST) is provided by natural gas auxiliary engines (except EST No. 5), which are connected to water wells via a right-angle gear connection. This right-angle gear connection is manually engaged during a power outage to operate only the well it is connected to. Most of the existing engines are over 30 years of age with several over 40 years of age. Due to the age of this equipment, parts are becoming scarce, and issues are taking longer to be repaired. SJRA Woodlands Division has implemented a program to replace existing auxiliary engines with natural gas or diesel generators (as the sites permit) at 12 sites comprising 23 wells. Replacing the existing auxiliary engines with generators allows for either water well on the site to be powered, generators to operate automatically in a power outage, and parts to be readily available.</p> <p>This project will install one generator well site, which has to be sized to run the largest well at the site. Costs were based on a previous installation costs at other SJRA facilities of the approximate generator size needed for running one 450 HP well motor which is 600 kW.</p>													
PROJECT SCHEDULE				DELIVERY		FUNDING							
Initiate Cons. Selection:		FY 2032		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		FY 2032		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS								
Final Proposal Docs:		FY 2032		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R								
Proposals/Bids Received:		FY 2032		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		FY 2033			<input type="checkbox"/> OTHER								
Substantial Completion:		FY 2034											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 88,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 88,000	\$ -	\$ -	\$ -	
Engineering/Design	\$ 88,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 88,000	\$ -	\$ -	\$ -	
Construction	\$ 926,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 456,000	\$ 470,000	\$ -	
CPS, CM&I, and CMT	\$ 93,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 46,000	\$ 47,000	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 1,195,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 176,000	\$ 502,000	\$ 517,000	\$ -	


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
Water Well Nos. 24 and 37 Rehabilitation				WA33WR		2033-2034			The Woodlands				
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>Water Well Nos. 24 and 37 have been identified for this project to have well rehabilitation performed and pumping equipment replaced. INTERA Incorporated produced a Water Well Master Plan in 2022. Based this master plan schedule identified, Well Nos. 24 and 37 for water well rehabilitation and equipment replacement for FY2033-2034. For the two wells, the pumping equipment will be removed and inspected, and the a video of the well will be performed to identify well rehabilitation needs. The project will include replacement of pump and well equipment; wire brushing the well screen section; and jetting out and removing fill material from the bottom of the well. Since the Water Well No. 37 pumping equipment will be replaced, the new well pump will be placed 50 feet lower per the recommendations of the master plan. No increase in well capacity is planned.</p> <p>Water Well No. 24 - Evangeline Aquifer; Design GPM: 900; Last Rehab: 2011; Current GPM: 760 Status: In-Service</p> <p>Water Well No. 37 - Jasper Aquifer; Design GPM: 1,500; Last Rehab: 2014; Current GPM: 1,610 Status: In-Service</p> <p>Costs are based on previous well rehabilitation projects of similar scope and pricing to lower the well pump.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		FY 2033		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		FY 2033		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS								
Final Proposal Docs:		FY 2033		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R								
Proposals/Bids Received:		FY 2033		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		FY 2033			<input type="checkbox"/> OTHER								
Substantial Completion:		FY 2034											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 66,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 66,000	\$ -	\$ -	
Construction	\$ 1,347,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 329,000	\$ 1,018,000	\$ -	
CPS, CM&I, and CMT	\$ 67,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 16,000	\$ 51,000	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 1,480,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 411,000	\$ 1,069,000	\$ -	



*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
Elevated Storage Tank No. 2 Rehabilitation				WAET2R		2033-2034			The Woodlands				
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>Elevated Storage Tank No. 2 is a 1,000,000 gallon tank and was constructed in 1982. Based on an engineering report completed in 2013, the exterior and interior coating systems were replaced in 2020 per the engineer's recommendation. A follow-up inspection of the tank will be completed in FY2026 to identify the need and scope for any additional rehabilitation work. Anticipated rehabilitation of the tank includes recoating of the tank exterior and interior surfaces for maintenance and to continue to protect the exterior and interior from corrosion. Additionally, modifications will be identified and installed for the future installation of water re-circulation equipment.</p> <p>To protect the metal structure from corrosion and to extend the useful life of the tank, periodic protective coating system replacement is required. The epoxy interior coating systems are anticipated to meet their protective value in about 12-15 years and require system replacement in order to continue to provide adequate corrosion protection. The useful life of the fluoropolymer exterior coating is expected to be 10-12 years.</p> <p>Projected costs are based on previous work conducted on the six Woodlands Division elevated storage tanks and industry pricing received from a third-party consultant in 2023, adjusted for inflation.</p>													
				PROJECT SCHEDULE				DELIVERY		FUNDING			
				Initiate Cons. Selection:		FY 2033		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M				
PSA/WO Issued:		FY 2033		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS								
Final Proposal Docs:		FY 2033		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R								
Proposals/Bids Received:		FY 2033		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		FY 2033			<input type="checkbox"/> OTHER								
Substantial Completion:		FY 2034											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 129,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 129,000	\$ -	\$ -	
Engineering/Design	\$ 129,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 129,000	\$ -	\$ -	
Construction	\$ 1,322,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 117,000	\$ 1,205,000	\$ -	
CPS, CM&I, and CMT	\$ 133,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 12,000	\$ 121,000	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 1,713,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 387,000	\$ 1,326,000	\$ -	


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
Elevated Storage Tank No. 1 Rehabilitation				WAET1R		2034-2035			The Woodlands				
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>Elevated Storage Tank No. 1 is a 500,000 gallon tank and was constructed in 1977. Based on an engineering report completed in 2013, the exterior and interior coating systems were replaced in 2021 per the engineer's recommendation. A follow-up inspection of the tank will be completed in FY2026 to identify the need and scope for any additional rehabilitation work. Anticipated rehabilitation of the tank includes recoating of the tank exterior and interior surfaces for maintenance and to continue to protect the exterior and interior from corrosion. Additionally, modifications will be identified and installed for the future installation of water re-circulation equipment.</p> <p>To protect the metal structure from corrosion and to extend the useful life of the tank, periodic protective coating system replacement is required. The epoxy interior coating systems are anticipated to meet their protective value in about 12-15 years and require system replacement in order to continue to provide adequate corrosion protection. The useful life of the fluoropolymer exterior coating is expected to be 10-12 years.</p> <p>Projected costs are based on previous work conducted on the six Woodlands Division elevated storage tanks and industry pricing received from a third-party consultant in 2023, adjusted for inflation.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		FY 2034		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		FY 2034		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS								
Final Proposal Docs:		FY 2034		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R								
Proposals/Bids Received:		FY 2034		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		FY 2034			<input type="checkbox"/> OTHER								
Substantial Completion:		FY 2035											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 81,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 81,000	\$ -	
Engineering/Design	\$ 81,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 81,000	\$ -	
Construction	\$ 1,660,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 147,000	\$ 1,513,000	
CPS, CM&I, and CMT	\$ 166,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 15,000	\$ 151,000	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 1,988,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 324,000	\$ 1,664,000	


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID	FISCAL YEAR	DIVISION						
Water Well Site Generator - Project 3				WA3WGN	2034-2035	The Woodlands						
PROJECT DESCRIPTION				PROJECT MAP/PICTURE								
<p>The San Jacinto River Authority (SJRA) Woodlands Division owns and operates thirty-seven (37) groundwater wells. The groundwater produced by these wells is conveyed to the five (5) water plants where it is mixed with surface water, chlorinated, and pumped into the distribution system.</p> <p>As surface water is considered a supplemental source, the Woodlands Division must have the ability to produce sufficient groundwater to provide the needs of The Woodlands if surface water is not available to comply with TCEQ regulations. Automated standby power is the solution during power outages.</p> <p>Backup power at off-site (non-water plant) well locations and wells at elevated storage tank sites (EST) is provided by natural gas auxiliary engines (except EST No. 5), which are connected to water wells via a right-angle gear connection. This right-angle gear connection is manually engaged during a power outage to operate only the well it is connected to. Most of the existing engines are over 30 years of age with several over 40 years of age. Due to the age of this equipment, parts are becoming scarce, and issues are taking longer to be repaired. SJRA Woodlands Division has implemented a program to replace existing auxiliary engines with natural gas or diesel generators (as the sites permit) at 12 sites comprising 23 wells. Replacing the existing auxiliary engines with generators allows for either water well on the site to be powered, generators to operate automatically in a power outage, and parts to be readily available.</p> <p>This project will install one generator well site, which has to be sized to run the largest well at the site. Costs were based on a previous installation costs at other SJRA facilities of the approximate generator size needed for running one 450 HP well motor which is 600 kW.</p>												
PROJECT SCHEDULE				DELIVERY	FUNDING							
Initiate Cons. Selection:	FY 2034	<input checked="" type="checkbox"/>	CSP	<input type="checkbox"/>	O&M							
PSA/WO Issued:	FY 2034	<input type="checkbox"/>	QUOTES	<input type="checkbox"/>	BONDS							
Final Proposal Docs:	FY 2034	<input type="checkbox"/>	PROFESSIONAL	<input checked="" type="checkbox"/>	R&R							
Proposals/Bids Received:	FY 2034	<input type="checkbox"/>	OTHER	<input type="checkbox"/>	GRANTS							
Constr. Contract to Board:	FY 2035	<input type="checkbox"/>		<input type="checkbox"/>	OTHER							
Substantial Completion:	FY 2035											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035
Planning/Permitting/PER	\$ 114,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 114,000	\$ -
Engineering/Design	\$ 114,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 114,000	\$ -
Construction	\$ 1,191,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 227,000	\$ 964,000
CPS, CM&I, and CMT	\$ 119,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 23,000	\$ 96,000
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total	\$ 1,538,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 478,000	\$ 1,060,000

*Budget includes 30% contingency, and 3% inflation per year.


PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
Water Well Nos. 12 and 28 Rehabilitation				WA34WR		2034-2035			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>Water Well Nos. 12 and 28 have been identified for this project to have well rehabilitation performed and pumping equipment replaced. INTERA Incorporated produced a Water Well Master Plan in 2022. Based this master plan schedule identified, Well Nos. 12 and 28 for water well rehabilitation and equipment replacement for FY2034-2035. For the two wells, the pumping equipment will be removed and inspected, and the a video of the well will be performed to identify well rehabilitation needs. The project will include replacement of pump and well equipment; wire brushing the well screen section; and jetting out and removing fill material from the bottom of the well. No pump lowering or increase in well capacity is planned.</p> <p>Water Well No. 12 - Evangeline Aquifer; Design GPM: 1,000; Last Rehab: 2012; Current GPM: 881 Status: In-Service</p> <p>Water Well No. 28 - Evangeline Aquifer; Design GPM: 750; Installed: 2007; Current GPM: 702 Status: In-Service</p> <p>Costs are based on previous well rehabilitation projects of similar scope.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:	FY 2034	<input checked="" type="checkbox"/>	CSP	<input type="checkbox"/>	O&M								
PSA/WO Issued:	FY 2034	<input type="checkbox"/>	QUOTES	<input type="checkbox"/>	BONDS								
Final Proposal Docs:	FY 2034	<input type="checkbox"/>	PROFESSIONAL	<input checked="" type="checkbox"/>	R&R								
Proposals/Bids Received:	FY 2034	<input type="checkbox"/>	OTHER	<input type="checkbox"/>	GRANTS								
Constr. Contract to Board:	FY 2034	<input type="checkbox"/>		<input type="checkbox"/>	OTHER								
Substantial Completion:	FY 2035												
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 59,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 59,000	\$ -	
Construction	\$ 1,213,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 339,000	\$ 874,000	
CPS, CM&I, and CMT	\$ 61,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 17,000	\$ 44,000	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 1,333,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 415,000	\$ 918,000	

*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
Water Well Nos. 17 and 39 Rehabilitation				WA35WR		2035-2036			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>Water Well Nos. 17 and 39 have been identified for this project to have well rehabilitation performed and pumping equipment replaced. INTERA Incorporated produced a Water Well Master Plan in 2022. Based this master plan schedule identified, Well Nos. 17 and 39 for water well rehabilitation and equipment replacement for FY2035-2036. For the two wells, the pumping equipment will be removed and inspected, and the a video of the well will be performed to identify well rehabilitation needs. The project will include replacement of pump and well equipment; wire brushing the well screen section; and jetting out and removing fill material from the bottom of the well. Since the Water Well Nos. 17 and 39 pumping equipment will be replaced, the new well pump will be placed 50 feet and 100 feet lower respectively per the recommendations of the master plan. As a result, the motor on Water Well No. 39 will have to be increased from 400 HP to 450 HP. No increase in well capacity is planned.</p> <p>Water Well No. 17 - Jasper Aquifer; Design GPM: 1,500; Last Rehab: 2016; Current GPM: 1,670 Status: In-Service</p> <p>Water Well No. 39 - Jasper Aquifer; Design GPM: 2,000; Installed: 2012; Current GPM: 1,740 Status: In-Service</p> <p>Costs are based on previous well rehabilitation projects of similar scope, lowering the well pumps, and pricing to replace the well motor for Water Well No. 39.</p>													
						PROJECT SCHEDULE				DELIVERY	FUNDING		
						Initiate Cons. Selection:		FY 2035		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M		
PSA/WO Issued:		FY 2035		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS								
Final Proposal Docs:		FY 2035		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R								
Proposals/Bids Received:		FY 2035		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		FY 2035			<input type="checkbox"/> OTHER								
Substantial Completion:		FY 2036											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 16,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 16,000	
Construction	\$ 314,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 314,000	
CPS, CM&I, and CMT	\$ 16,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 16,000	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 346,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 346,000	


*Budget includes 30% contingency, and 3% inflation per year.

**Project extends into FY2036. Total project cost will be \$1,707,000.


PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION					
Town Center Water Line Replacement				WA21WL		2021-TBD			The Woodlands					
PROJECT DESCRIPTION						PROJECT MAP/PICTURE								
<p>This project is part of a phased asset management approach to continuously replace water lines that are beyond their service life, have had a number of repairs, and based on a 2024-2025 condition based assessment of the AC water lines in The Woodlands that is underway. The current plan is to replace all asbestos cement (AC) water lines within the next 10-15 years. The AC lines will be replaced with PVC or HDPE lines. The results of the assessment will be presented to The Woodlands MUDs to determine a path forward for AC water line replacement prioritization. This scope and schedule of the projects in this project plan could be adjusted based upon the results of the assessment, and would be reflected in future project plans. The existing distribution system contains approximately 48 miles of asbestos cement (AC) lines. Approximately 90% of all these water lines are more than 40 years old. Historically, SJRA has experienced on average 9 failures per year, and is trending upward.</p> <p>Approximately 14,000 linear feet (2.7 miles) of 12-inch AC water mains in the Grogan's Mill and Metro Center areas along Six Pines Drive between North Millbend Drive and Timberloch Place, along Lake Woodlands Drive from Hughes Landing Blvd to Pinecroft Drive, and along Grogan's Mill Road from Research Forest Drive to Woodlands Parkway were identified for this project scope. Costs are based on a Engineers Opinion of Construction Cost during the Final Design phase of this project from early 2023, with inflation and contingency added. Also, easement (land) acquisition will be required for adjusting position of lines and construction access with budget based upon existing cost estimates for similar areas (see WATCEA). Based on the outcome of the AC Water Line Condition Based Assessment, the timing and scope of this replacement could be adjusted. The preliminary and final design phases were funded by R&R funds.</p>														
PROJECT SCHEDULE				DELIVERY	FUNDING									
Initiate Cons. Selection:		Completed		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:		Completed		<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS									
Final Proposal Docs:		TBD		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R									
Proposals/Bids Received:		TBD		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		TBD			<input type="checkbox"/> OTHER									
Substantial Completion:		TBD												
BUDGET**	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035		
Planning/Permitting/PER*	\$ 299,315	\$ 299,315	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Engineering/Design*	\$ 528,238	\$ 348,334	\$ 179,904	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Construction	\$ 15,723,000	\$ -	\$ -	\$ 9,944,000	\$ 5,779,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
CPS, CM&I, and CMT	\$ 1,572,000	\$ -	\$ -	\$ 994,000	\$ 578,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Total	\$ 18,122,553	\$ 647,649	\$ 179,904	\$ 10,938,000	\$ 6,357,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		

*In Previous funding, was R&R funded for design for \$647,649 total, and in 2026 an additional \$179,904 will be R&R funded for design.


**Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION						
N. Town Center and S. Grogans Mill Road Water Line Replacement				WA23WL		2026-TBD			The Woodlands						
PROJECT DESCRIPTION						PROJECT MAP/PICTURE									
<p>This project is part of a phased asset management approach to continuously replace water lines that are beyond their service life, have had a number of repairs, and based on a 2024-2025 condition based assessment of the AC water lines in The Woodlands that is underway. The current plan is to replace all asbestos cement (AC) water lines within the next 10-15 years. The AC lines will be replaced with PVC or HDPE lines. The results of the assessment will be presented to The Woodlands MUDs to determine a path forward for AC water line replacement prioritization. This scope and schedule of the projects in this project plan could be adjusted based upon the results of the assessment, and would be reflected in future project plans.</p> <p>The existing distribution system contains approximately 48 miles of asbestos cement (AC) lines. Approximately 90% of all these water lines are more than 40 years old. Historically, SJRA has experienced on average 9 failures per year, and is trending upward.</p> <p>Approximately 27,000 linear feet (5 miles) of 12 and 16-inch AC water mains along Lake Front Circle and Pinecroft Drive between Grogan's Mill Road and IH-45 and along Grogan's Mill Road south of Woodlands Parkway were identified for this project scope. Costs are based on a Engineers Opinion of Construction Cost during the Final Design phase of this project from early 2023, with inflation and contingency added. Also, easement (land) acquisition will be required for adjusting position of lines and construction access with budget based upon existing cost estimates for similar areas. Based on the outcome of the AC Water Line Condition Based Assessment, the timing and scope of this replacement could be adjusted.</p>															
						PROJECT SCHEDULE				DELIVERY	FUNDING				
						Initiate Cons. Selection:		TBD		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M				
PSA/WO Issued:		TBD		<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS										
Final Proposal Docs:		TBD		<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R										
Proposals/Bids Received:		TBD		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS										
Constr. Contract to Board:		TBD			<input type="checkbox"/> OTHER										
Substantial Completion:		TBD													
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035			
Planning/Permitting/PER	\$ 1,705,000	\$ -	\$ -	\$ 1,705,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -			
Engineering/Design	\$ 1,717,000	\$ -	\$ -	\$ 1,278,000	\$ 439,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -			
Construction	\$ 16,322,000	\$ -	\$ -	\$ -	\$ 3,512,000	\$ 12,810,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -			
CPS, CM&I, and CMT	\$ 1,632,000	\$ -	\$ -	\$ -	\$ 351,000	\$ 1,281,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -			
Land Acquisition	\$ 1,523,000	\$ -	\$ -	\$ 426,000	\$ 1,097,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -			
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -			
Total	\$ 22,899,000	\$ -	\$ -	\$ 3,409,000	\$ 5,399,000	\$ 14,091,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -			



*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION					
Panther Creek Area Water Line Replacement				WA24WL		2026-TBD			The Woodlands					
PROJECT DESCRIPTION						PROJECT MAP/PICTURE								
<p>This project is part of a phased asset management approach to continuously replace water lines that are beyond their service life, have had a number of repairs, and based on a 2024-2025 condition based assessment of the AC water lines in The Woodlands that is underway. The current plan is to replace all asbestos cement (AC) water lines within the next 10-15 years. The AC lines will be replaced with PVC or HDPE lines. The results of the assessment will be presented to The Woodlands MUDs to determine a path forward for AC water line replacement prioritization. This scope and schedule of the projects in this project plan could be adjusted based upon the results of the assessment, and would be reflected in future project plans.</p> <p>The existing distribution system contains approximately 48 miles of asbestos cement (AC) lines. Approximately 90% of all these water lines are more than 40 years old. Historically, SJRA has experienced on average 9 failures per year, and is trending upward.</p> <p>Approximately 32,000 linear feet (6 miles) of 12, 16, 20 24, and 30-inch AC, Steel Reinforced Concrete Pipe (SRPC), and Ductile Iron (DI) pipe along New Trails Dr., Technology Forest Blvd., Research Forest Dr., Gosling Rd., Shadowbend Circle, Quiet Oak Circle, and Golden Shadow Circle were identified for this project scope. Costs are based on a Engineers Opinion of Construction Cost during the Final Design phase of this project from early 2023, with inflation and contingency added. Also, easement (land) acquisition will be required for adjusting position of lines and construction access with budget based upon existing cost estimates for similar areas. Based on the outcome of the AC Water Line Condition Based Assessment, the timing and scope of this replacement could be adjusted.</p>														
						PROJECT SCHEDULE			DELIVERY		FUNDING			
						Initiate Cons. Selection:			TBD	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M			
PSA/WO Issued:			TBD	<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS									
Final Proposal Docs:			TBD	<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R									
Proposals/Bids Received:			TBD	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:			TBD		<input type="checkbox"/> OTHER									
Substantial Completion:			TBD											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035		
Planning/Permitting/PER	\$ 2,273,000	\$ -	\$ -	\$ 2,273,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Engineering/Design	\$ 2,307,000	\$ -	\$ -	\$ 1,136,000	\$ 1,171,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Construction	\$ 22,761,000	\$ -	\$ -	\$ -	\$ 5,523,000	\$ 11,378,000	\$ 5,860,000	\$ -	\$ -	\$ -	\$ -	\$ -		
CPS, CM&I, and CMT	\$ 2,276,000	\$ -	\$ -	\$ -	\$ 552,000	\$ 1,138,000	\$ 586,000	\$ -	\$ -	\$ -	\$ -	\$ -		
Land Acquisition	\$ 1,528,000	\$ -	\$ -	\$ 284,000	\$ 1,244,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Total	\$ 31,145,000	\$ -	\$ -	\$ 3,693,000	\$ 8,490,000	\$ 12,516,000	\$ 6,446,000	\$ -	\$ -	\$ -	\$ -	\$ -		


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION					
Water Plant No. 2 Ground Storage Tank No. 1 Replacement				WA2GT1		2029-2031			The Woodlands					
PROJECT DESCRIPTION						PROJECT MAP/PICTURE								
<p>Ground Storage Tank 1 (GST No. 1) at Water Plant 2 is a concrete storage tank with a capacity of 2.0 million gallons (MG), and was originally constructed in 1982. In 2017, structural deficiencies and leakage were identified during an annual inspection and repairs made to maintain service life. However, the overall structural integrity of the tank is unknown. The typical useful life for concrete ground storage tanks storing potable water is 50 years, which for GST No. 1 will occur in 2032. For planning purposes, it is anticipated that a full replacement of the tank will need to occur; however, a comprehensive structural analysis will occur in FY2029 to determine the tank's long-term viability.</p> <p>With anticipation that this GST will need to be replaced, the project includes demolition of the existing 2 MG concrete ground storage tank, construction of a new 2.0 MG concrete ground storage tank, and replacement of associated piping and appurtenances.</p> <p>The costs for this project were based upon a similar project where a 2 MG concrete ground storage tank was replaced and from updated 2024 pricing from tank contractors.</p>														
PROJECT SCHEDULE				DELIVERY	FUNDING									
Initiate Cons. Selection:		FY 2029		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:		FY 2029		<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS									
Final Proposal Docs:		FY 2029		<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R									
Proposals/Bids Received:		FY 2029		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		FY 2030			<input type="checkbox"/> OTHER									
Substantial Completion:		FY 2031												
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035		
Planning/Permitting/PER	\$ 466,000	\$ -	\$ -	\$ -	\$ -	\$ 466,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Engineering/Design	\$ 466,000	\$ -	\$ -	\$ -	\$ -	\$ 466,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Construction	\$ 4,811,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 4,317,000	\$ 494,000	\$ -	\$ -	\$ -	\$ -		
CPS, CM&I, and CMT	\$ 481,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 432,000	\$ 49,000	\$ -	\$ -	\$ -	\$ -		
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Total	\$ 6,224,000	\$ -	\$ -	\$ -	\$ -	\$ 932,000	\$ 4,749,000	\$ 543,000	\$ -	\$ -	\$ -	\$ -		


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION					
Conference/Resort Area Water Line Replacement				WA25WL		2029-TBD			The Woodlands					
PROJECT DESCRIPTION						PROJECT MAP/PICTURE								
<p>This project is part of a phased asset management approach to continuously replace water lines that are beyond their service life, have had a number of repairs, and based on a 2024-2025 condition based assessment of the AC water lines in The Woodlands that is underway. The current plan is to replace all asbestos cement (AC) water lines within the next 10-15 years. The AC lines will be replaced with PVC or HDPE lines. The results of the assessment will be presented to The Woodlands MUDs to determine a path forward for AC water line replacement prioritization. This scope and schedule of the projects in this project plan could be adjusted based upon the results of the assessment, and would be reflected in future project plans.</p> <p>The existing distribution system contains approximately 48 miles of asbestos cement (AC) lines. Approximately 90% of all these water lines are more than 40 years old. Historically, SJRA has experienced on average 9 failures per year, and is trending upward.</p> <p>Approximately 13,000 linear feet (2.5 miles) of 12 and 16-inch AC water mains in the Village of Grogan's Mill west of Grogan's Mill Road were identified for this project scope. Costs are based on a Engineers Opinion of Construction Cost during the Final Design phase of this project from early 2023, with inflation and contingency added. Also, easement (land) acquisition will be required for adjusting position of lines and construction access with budget based upon existing cost estimates for similar areas. Based on the outcome of the AC Water Line Condition Based Assessment, the timing and scope of this replacement could be adjusted.</p>														
PROJECT SCHEDULE				DELIVERY	FUNDING									
Initiate Cons. Selection:	TBD	<input checked="" type="checkbox"/>	CSP	<input type="checkbox"/>	O&M									
PSA/WO Issued:	TBD	<input type="checkbox"/>	QUOTES	<input checked="" type="checkbox"/>	BONDS									
Final Proposal Docs:	TBD	<input type="checkbox"/>	PROFESSIONAL	<input type="checkbox"/>	R&R									
Proposals/Bids Received:	TBD	<input type="checkbox"/>	OTHER	<input type="checkbox"/>	GRANTS									
Constr. Contract to Board:	TBD			<input type="checkbox"/>	OTHER									
Substantial Completion:	TBD													
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035		
Planning/Permitting/PER	\$ 1,145,000	\$ -	\$ -	\$ -	\$ -	\$ 1,145,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Engineering/Design	\$ 1,156,000	\$ -	\$ -	\$ -	\$ -	\$ 802,000	\$ 354,000	\$ -	\$ -	\$ -	\$ -	\$ -		
Construction	\$ 11,975,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 5,899,000	\$ 6,076,000	\$ -	\$ -	\$ -	\$ -		
CPS, CM&I, and CMT	\$ 1,198,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 590,000	\$ 608,000	\$ -	\$ -	\$ -	\$ -		
Land Acquisition	\$ 1,560,000	\$ -	\$ -	\$ -	\$ -	\$ 784,000	\$ 776,000	\$ -	\$ -	\$ -	\$ -	\$ -		
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Total	\$ 17,034,000	\$ -	\$ -	\$ -	\$ -	\$ 2,731,000	\$ 7,619,000	\$ 6,684,000	\$ -	\$ -	\$ -	\$ -		


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR		DIVISION					
Sawmill Road and Grogans Point Drive Water Line Replacement				WA26WL		2029-TBD		The Woodlands					
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>This project is part of a phased asset management approach to continuously replace water lines that are beyond their service life, have had a number of repairs, and based on a 2024-2025 condition based assessment of the AC water lines in The Woodlands that is underway. The current plan is to replace all asbestos cement (AC) water lines within the next 10-15 years. The AC lines will be replaced with PVC or HDPE lines. The results of the assessment will be presented to The Woodlands MUDs to determine a path forward for AC water line replacement prioritization. This scope and schedule of the projects in this project plan could be adjusted based upon the results of the assessment, and would be reflected in future project plans.</p> <p>The existing distribution system contains approximately 48 miles of asbestos cement (AC) lines. Approximately 90% of all these water lines are more than 40 years old. Historically, SJRA has experienced on average 9 failures per year, and is trending upward.</p> <p>Approximately 21,000 linear feet (4 miles) of 12 and 16-inch water mains along Sawmill Road, South Millbend Dr., Sawdust Road, and Grogan's Point Road were identified for this project scope. Costs are based on a Engineers Opinion of Construction Cost during the Final Design phase of this project from early 2023, with inflation and contingency added. Also, easement (land) acquisition will be required for adjusting position of lines and construction access with budget based upon existing cost estimates for similar areas. Based on the outcome of the AC Water Line Condition Based Assessment, the timing and scope of this replacement could be adjusted.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		TBD	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:		TBD	<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS									
Final Proposal Docs:		TBD	<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R									
Proposals/Bids Received:		TBD	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		TBD		<input type="checkbox"/> OTHER									
Substantial Completion:		TBD											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 1,130,000	\$ -	\$ -	\$ -	\$ -	\$ 1,130,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 1,156,000	\$ -	\$ -	\$ -	\$ -	\$ 283,000	\$ 873,000	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 11,817,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 5,821,000	\$ 5,996,000	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 1,182,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 582,000	\$ 600,000	\$ -	\$ -	\$ -	\$ -	
Land Acquisition	\$ 1,573,000	\$ -	\$ -	\$ -	\$ -	\$ 603,000	\$ 970,000	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 16,858,000	\$ -	\$ -	\$ -	\$ -	\$ 2,016,000	\$ 8,246,000	\$ 6,596,000	\$ -	\$ -	\$ -	\$ -	



*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR		DIVISION									
Millbend Water Line Replacement				WA27WL		2030-TBD		The Woodlands									
PROJECT DESCRIPTION				PROJECT MAP/PICTURE													
<p>This project is part of a phased asset management approach to continuously replace water lines that are beyond their service life, have had a number of repairs, and based on a 2024-2025 condition based assessment of the AC water lines in The Woodlands that is underway. The current plan is to replace all asbestos cement (AC) water lines within the next 10-15 years. The AC lines will be replaced with PVC or HDPE lines. The results of the assessment will be presented to The Woodlands MUDs to determine a path forward for AC water line replacement prioritization. This scope and schedule of the projects in this project plan could be adjusted based upon the results of the assessment, and would be reflected in future project plans.</p> <p>The existing distribution system contains approximately 48 miles of asbestos cement (AC) lines. Approximately 90% of all these water lines are more than 40 years old. Historically, SJRA has experienced on average 9 failures per year, and is trending upward.</p> <p>Approximately 25,500 linear feet (4.8 miles) of 12, 16 and 20-inch AC water mains in the Village of Grogan's Mill east of Grogan's Mill Road were identified for this project scope. Costs are based on a Engineers Opinion of Construction Cost during the Final Design phase of this project from early 2023, with inflation and contingency added. Also, easement (land) acquisition will be required for adjusting position of lines and construction access with budget based upon existing cost estimates for similar areas. Based on the outcome of the AC Water Line Condition Based Assessment, the timing and scope of this replacement could be adjusted.</p>																	
				PROJECT SCHEDULE				DELIVERY		FUNDING							
				Initiate Cons. Selection:		TBD		<input checked="" type="checkbox"/> CSP		<input type="checkbox"/> O&M							
PSA/WO Issued:		TBD		<input type="checkbox"/> QUOTES		<input checked="" type="checkbox"/> BONDS											
Final Proposal Docs:		TBD		<input type="checkbox"/> PROFESSIONAL		<input type="checkbox"/> R&R											
Proposals/Bids Received:		TBD		<input type="checkbox"/> OTHER		<input type="checkbox"/> GRANTS											
Constr. Contract to Board:		TBD				<input type="checkbox"/> OTHER											
Substantial Completion:		TBD															
BUDGET*		TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035				
Planning/Permitting/PER		\$ 1,459,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,459,000	\$ -	\$ -	\$ -	\$ -	\$ -				
Engineering/Design		\$ 1,490,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 438,000	\$ 1,052,000	\$ -	\$ -	\$ -	\$ -				
Construction		\$ 15,345,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 4,509,000	\$ 10,836,000	\$ -	\$ -	\$ -				
CPS, CM&I, and CMT		\$ 1,535,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 451,000	\$ 1,084,000	\$ -	\$ -	\$ -				
Land Acquisition		\$ 1,580,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 621,000	\$ 959,000	\$ -	\$ -	\$ -	\$ -				
Equipment Purchase		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -				
Total		\$ 21,409,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,518,000	\$ 6,971,000	\$ 11,920,000	\$ -	\$ -	\$ -				


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR		DIVISION					
West Lake Area Water Line Replacement				WA28WL		2030-TBD		The Woodlands					
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>This project is part of a phased asset management approach to continuously replace water lines that are beyond their service life, have had a number of repairs, and based on a 2024-2025 condition based assessment of the AC water lines in The Woodlands that is underway. The current plan is to replace all asbestos cement (AC) water lines within the next 10-15 years. The AC lines will be replaced with PVC or HDPE lines. The results of the assessment will be presented to The Woodlands MUDs to determine a path forward for AC water line replacement prioritization. This scope and schedule of the projects in this project plan could be adjusted based upon the results of the assessment, and would be reflected in future project plans.</p> <p>The existing distribution system contains approximately 48 miles of asbestos cement (AC) lines. Approximately 90% of all these water lines are more than 40 years old. Historically, SJRA has experienced on average 9 failures per year, and is trending upward.</p> <p>Approximately 21,000 linear feet (4 miles) of 12 and 24-inch AC and Steel Reinforced Concrete Pipe (SRPC) pipe along Woodlands Parkway, East Panther Creek Drive, West Isle Place, and Lake Woodlands Drive were identified for this project scope. Costs are based on a Engineers Opinion of Construction Cost during the Final Design phase of this project from early 2023, with inflation and contingency added. Also, easement (land) acquisition will be required for adjusting position of lines and construction access with budget based upon existing cost estimates for similar areas. Based on the outcome of the AC Water Line Condition Based Assessment, the timing and scope of this replacement could be adjusted.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		TBD		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		TBD		<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS								
Final Proposal Docs:		TBD		<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R								
Proposals/Bids Received:		TBD		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		TBD			<input type="checkbox"/> OTHER								
Substantial Completion:		TBD											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 1,273,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,273,000	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 1,300,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 382,000	\$ 918,000	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 13,346,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 5,244,000	\$ 8,102,000	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 1,334,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 524,000	\$ 810,000	\$ -	\$ -	\$ -	
Land Acquisition	\$ 1,575,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 776,000	\$ 799,000	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 18,828,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,431,000	\$ 7,485,000	\$ 8,912,000	\$ -	\$ -	\$ -	


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR		DIVISION				
Water Well No. 40				WAWW40		2030-2033		The Woodlands				
PROJECT DESCRIPTION				PROJECT MAP/PICTURE								
<p>The Woodlands uses a combination of groundwater and surface water to meet water demands in The Woodlands. As of 2025, two of Woodlands Division wells (Well Nos. 2 and 4) have been abandoned due to production issues, and prior to 2030, at least two more water wells (Well Nos. 1 and 6) in the Woodlands system are anticipated to be plugged and abandoned due to well construction issues, end of service life for the casing, and production issues. With a decrease in the amount of groundwater production capability, construction of a Upper Jasper Aquifer water well is recommended. Land may need to be acquired to allow for an estimated 1/2 acre site. The proposed water well is planned to be capable of producing 3,000 gallons per minute. The site will also include a backup generator, which is anticipated to be approximately a 600 kW unit.</p> <p>This project will also include the installation of a 24-inch well collection line from the water well to the nearest SJRA Woodlands Division water plant. The water well cost is based on previous water well installations as well as estimates from third-party consultants. The well collection line cost is based on installing approximately 2,500 linear feet of 24-inch well collection, with unit pricing from third-party consultants.</p>												
PROJECT SCHEDULE			DELIVERY	FUNDING								
Initiate Cons. Selection:	FY 2029	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:	FY 2030	<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS									
Final Proposal Docs:	FY 2030	<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R									
Proposals/Bids Received:	FY 2030	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:	FY 2031		<input type="checkbox"/> OTHER									
Substantial Completion:	FY 2033											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035
Planning/Permitting/PER	\$ 849,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 849,000	\$ -	\$ -	\$ -	\$ -	\$ -
Engineering/Design	\$ 862,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 425,000	\$ 437,000	\$ -	\$ -	\$ -	\$ -
Construction	\$ 9,012,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,109,000	\$ 4,665,000	\$ 2,238,000	\$ -	\$ -
CPS, CM&I, and CMT	\$ 901,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 211,000	\$ 466,000	\$ 224,000	\$ -	\$ -
Land Acquisition	\$ 301,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 301,000	\$ -	\$ -	\$ -	\$ -	\$ -
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total	\$ 11,925,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,575,000	\$ 2,757,000	\$ 5,131,000	\$ 2,462,000	\$ -	\$ -


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION					
West Panther Creek Area Water Line Replacement				WA29WL		2033-TBD			The Woodlands					
PROJECT DESCRIPTION						PROJECT MAP/PICTURE								
<p>This project is part of a phased asset management approach to continuously replace water lines that are beyond their service life, have had a number of repairs, and based on a 2024-2025 condition based assessment of the AC water lines in The Woodlands that is underway. The current plan is to replace all asbestos cement (AC) water lines within the next 10-15 years. The AC lines will be replaced with PVC or HDPE lines. The results of the assessment will be presented to The Woodlands MUDs to determine a path forward for AC water line replacement prioritization. This scope and schedule of the projects in this project plan could be adjusted based upon the results of the assessment, and would be reflected in future project plans.</p> <p>The existing distribution system contains approximately 48 miles of asbestos cement (AC) lines. Approximately 90% of all these water lines are more than 40 years old. Historically, SJRA has experienced on average 9 failures per year, and is trending upward.</p> <p>Approximately 19,700 linear feet (3.7 miles) of 12, 16 and 24-inch AC and Steel Reinforced Concrete Pipe (SRPC) pipe along Gosling Road, West Panther Creek Drive, Interfaith Way, Split Rock Road, and Lake Woodlands Drive were identified for this project scope. Costs are based on a Engineers Opinion of Construction Cost during the Final Design phase of this project from early 2023, with inflation and contingency added. Also, easement (land) acquisition will be required for adjusting position of lines and construction access with budget based upon existing cost estimates for similar areas. Based on the outcome of the AC Water Line Condition Based Assessment, the timing and scope of this replacement could be adjusted.</p>														
						PROJECT SCHEDULE			DELIVERY		FUNDING			
						Initiate Cons. Selection:			TBD		<input checked="" type="checkbox"/> CSP		<input type="checkbox"/> O&M	
PSA/WO Issued:			TBD		<input type="checkbox"/> QUOTES		<input checked="" type="checkbox"/> BONDS							
Final Proposal Docs:			TBD		<input type="checkbox"/> PROFESSIONAL		<input type="checkbox"/> R&R							
Proposals/Bids Received:			TBD		<input type="checkbox"/> OTHER		<input type="checkbox"/> GRANTS							
Constr. Contract to Board:			TBD				<input type="checkbox"/> OTHER							
Substantial Completion:			TBD											
BUDGET*		TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER		\$ 1,391,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,391,000	\$ -	\$ -	
Engineering/Design		\$ 1,420,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 417,000	\$ 1,003,000	\$ -	
Construction		\$ 14,541,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 7,163,000	\$ 7,378,000	
CPS, CM&I, and CMT		\$ 1,454,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 716,000	\$ 738,000	
Land Acquisition		\$ 1,547,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 848,000	\$ 699,000	\$ -	
Equipment Purchase		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total		\$ 20,353,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,656,000	\$ 9,581,000	\$ 8,116,000	


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION								
South Panther Creek Area Water Line Replacement				WA30WL		2033-TBD			The Woodlands								
PROJECT DESCRIPTION						PROJECT MAP/PICTURE											
<p>This project is part of a phased asset management approach to continuously replace water lines that are beyond their service life, have had a number of repairs, and based on a 2024-2025 condition based assessment of the AC water lines in The Woodlands that is underway. The current plan is to replace all asbestos cement (AC) water lines within the next 10-15 years. The AC lines will be replaced with PVC or HDPE lines. The results of the assessment will be presented to The Woodlands MUDs to determine a path forward for AC water line replacement prioritization. This scope and schedule of the projects in this project plan could be adjusted based upon the results of the assessment, and would be reflected in future project plans.</p> <p>The existing distribution system contains approximately 48 miles of asbestos cement (AC) lines. Approximately 90% of all these water lines are more than 40 years old. Historically, SJRA has experienced on average 9 failures per year, and is trending upward.</p> <p>Approximately 23,000 linear feet (4.3 miles) of 12-inch AC pipe along South Panther Creek, Coralberry Road, Woodstock Circle Drive, Flintridge Drive, Rush Haven Drive, Falconwing Drive, and McCullough Circle were identified for this project scope. Costs are based on a Engineers Opinion of Construction Cost during the Final Design phase of this project from early 2023, with inflation and contingency added. Also, easement (land) acquisition will be required for adjusting position of lines and construction access with budget based upon existing cost estimates for similar areas. Based on the outcome of the AC Water Line Condition Based Assessment, the timing and scope of this replacement could be adjusted.</p>																	
						PROJECT SCHEDULE				DELIVERY		FUNDING					
						Initiate Cons. Selection:		TBD		<input checked="" type="checkbox"/> CSP		<input type="checkbox"/> O&M					
PSA/WO Issued:		TBD		<input type="checkbox"/> QUOTES		<input checked="" type="checkbox"/> BONDS											
Final Proposal Docs:		TBD		<input type="checkbox"/> PROFESSIONAL		<input type="checkbox"/> R&R											
Proposals/Bids Received:		TBD		<input type="checkbox"/> OTHER		<input type="checkbox"/> GRANTS											
Constr. Contract to Board:		TBD				<input type="checkbox"/> OTHER											
Substantial Completion:		TBD															
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035					
Planning/Permitting/PER	\$ 1,357,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,357,000	\$ -	\$ -					
Engineering/Design	\$ 1,385,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 407,000	\$ 978,000	\$ -					
Construction	\$ 14,186,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 6,988,000	\$ 7,198,000					
CPS, CM&I, and CMT	\$ 1,419,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 699,000	\$ 720,000					
Land Acquisition	\$ 1,552,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 678,000	\$ 874,000	\$ -					
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -					
Total	\$ 19,899,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,442,000	\$ 9,539,000	\$ 7,918,000					

*Budget includes 30% contingency, and 3% inflation per year.


PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION							
Trade Center Area Water Line Replacement				WA31WL		2033-TBD			The Woodlands							
PROJECT DESCRIPTION				PROJECT MAP/PICTURE												
<p>This project is part of a phased asset management approach to continuously replace water lines that are beyond their service life, have had a number of repairs, and based on a 2024-2025 condition based assessment of the AC water lines in The Woodlands that is underway. The current plan is to replace all asbestos cement (AC) water lines within the next 10-15 years. The AC lines will be replaced with PVC or HDPE lines. The results of the assessment will be presented to The Woodlands MUDs to determine a path forward for AC water line replacement prioritization. This scope and schedule of the projects in this project plan could be adjusted based upon the results of the assessment, and would be reflected in future project plans.</p> <p>The existing distribution system contains approximately 48 miles of asbestos cement (AC) lines. Approximately 90% of all these water lines are more than 40 years old. Historically, SJRA has experienced on average 9 failures per year, and is trending upward.</p> <p>Approximately 12,000 linear feet (2.3 miles) of 12 and 16-inch AC pipe along SH242 and Trade Center Parkway were identified for this project scope. Costs are based on a Engineers Opinion of Construction Cost during the Final Design phase of this project from early 2023, with inflation and contingency added. Also, easement (land) acquisition will be required for adjusting position of lines and construction access with budget based upon existing cost estimates for similar areas. Based on the outcome of the AC Water Line Condition Based Assessment, the timing and scope of this replacement could be adjusted.</p>																
				PROJECT SCHEDULE			DELIVERY	FUNDING								
				Initiate Cons. Selection:	TBD	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:	TBD	<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS													
Final Proposal Docs:	TBD	<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R													
Proposals/Bids Received:	TBD	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS													
Constr. Contract to Board:	TBD		<input type="checkbox"/> OTHER													
Substantial Completion:	TBD															
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035				
Planning/Permitting/PER	\$ 814,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 814,000	\$ -	\$ -				
Engineering/Design	\$ 826,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 407,000	\$ 419,000	\$ -				
Construction	\$ 8,512,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 4,193,000	\$ 4,319,000				
CPS, CM&I, and CMT	\$ 851,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 419,000	\$ 432,000				
Land Acquisition	\$ 1,564,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 848,000	\$ 716,000	\$ -				
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -				
Total	\$ 12,567,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,069,000	\$ 5,747,000	\$ 4,751,000				

*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION								
Cochran's Crossing Area Water Line Replacement				WA32WL		2034-TBD			The Woodlands								
PROJECT DESCRIPTION						PROJECT MAP/PICTURE											
<p>This project is part of a phased asset management approach to continuously replace water lines that are beyond their service life, have had a number of repairs, and based on a 2024-2025 condition based assessment of the AC water lines in The Woodlands that is underway. The current plan is to replace all asbestos cement (AC) water lines within the next 10-15 years. The AC lines will be replaced with PVC or HDPE lines. The results of the assessment will be presented to The Woodlands MUDs to determine a path forward for AC water line replacement prioritization. This scope and schedule of the projects in this project plan could be adjusted based upon the results of the assessment, and would be reflected in future project plans.</p> <p>The existing distribution system contains approximately 48 miles of asbestos cement (AC) lines. Approximately 90% of all these water lines are more than 40 years old. Historically, SJRA has experienced on average 9 failures per year, and is trending upward.</p> <p>Approximately 27,000 linear feet (5.2 miles) of 12, 16 and 20-inch AC and Ductile Iron (DI) pipe along Lake Woodlands Drive, Falconwing Drive, Sylvan Forest Drive, Shadowbend Place, Cochran's Crossing Drive, John Cooper Drive and Elevated Storage Tank No. 2 were identified for this project scope. Costs are based on a Engineers Opinion of Construction Cost during the Final Design phase of this project from early 2023, with inflation and contingency added. Also, easement (land) acquisition will be required for adjusting position of lines and construction access with budget based upon existing cost estimates for similar areas. Based on the outcome of the AC Water Line Condition Based Assessment, the timing and scope of this replacement could be adjusted.</p>																	
						PROJECT SCHEDULE				DELIVERY	FUNDING						
						Initiate Cons. Selection:		TBD		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M						
PSA/WO Issued:		TBD		<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS												
Final Proposal Docs:		TBD		<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R												
Proposals/Bids Received:		TBD		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS												
Constr. Contract to Board:		TBD			<input type="checkbox"/> OTHER												
Substantial Completion:		TBD															
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035					
Planning/Permitting/PER	\$ 1,887,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,887,000	\$ -					
Engineering/Design	\$ 1,915,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 943,000	\$ 972,000					
Construction	\$ 5,830,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 5,830,000					
CPS, CM&I, and CMT	\$ 583,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 583,000					
Land Acquisition	\$ 1,594,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 874,000	\$ 720,000					
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -					
Total	\$ 11,809,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 3,704,000	\$ 8,105,000					


*Budget includes 30% contingency, and 3% inflation per year.

**Project extends into FY2036. The total project cost is \$26,775,000.


PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION					
Woodlands Parkway Water Line Replacement				WAWPWL		2034-2037			The Woodlands					
PROJECT DESCRIPTION					PROJECT MAP/PICTURE									
<p>The 16 - 24-inch water line along Woodlands Parkway between FM 2978 and Carlton Woods Drive was installed in phases between 2000 and 2005. However, since that time, this water line has experienced approximately 30 breaks in locations along the entire alignment. Most of the failures that have occurred appear to have been a result of installation method, resulting in pipe movement over time, which ultimately results in failure, primarily starting at the fitting connections.</p> <p>The water line is anticipated to be replaced with a fused PVC or HDPE pipe primarily installed using trenchless methods. This will result in a pipe with few fittings.</p> <p>The costs were determined based upon recent construction pricing for water line pipe replacement of the same diameter and multiplying the length to be replace.</p> <p>Based on the outcome of the AC Water Line Condition Based Assessment, the timing of this replacement could be adjusted.</p>														
PROJECT SCHEDULE				DELIVERY	FUNDING									
Initiate Cons. Selection:		FY 2034	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M										
PSA/WO Issued:		FY 2034	<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS										
Final Proposal Docs:		FY 2035	<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R										
Proposals/Bids Received:		FY 2035	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS										
Constr. Contract to Board:		FY 2035		<input type="checkbox"/> OTHER										
Substantial Completion:		FY 2037												
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035		
Planning/Permitting/PER	\$ 1,625,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,625,000	\$ -		
Engineering/Design	\$ 1,674,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,674,000		
Construction	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
CPS, CM&I, and CMT	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Land Acquisition	\$ 1,594,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 874,000	\$ 720,000		
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Total	\$ 4,893,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,499,000	\$ 2,394,000		

*Budget includes 30% contingency, and 3% inflation per year.

**Project extends into FY2036 and FY2037. The total project cost is \$24,140,000.


PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
Lift Station Rehabilitation				WW21LS		2021-2035			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>Each year, a comprehensive evaluation of all thirty lift stations in The Woodlands is conducted. This evaluation includes visual inspection and condition assessment ranking of each lift station by SJRA staff which results in a prioritized list of lift stations to be rehabilitation. In addition, the Sanitary Sewer Transmission Asset Renewal Program included a comprehensive condition assessment, with results incorporated into SJRA's prioritized list. Based on this list, several lift stations were identified as needing minor rehabilitation work, such as replacement or addition of the wet well coating, minor structural repairs, minor electrical improvements, and replacement of panels. This project, and lift station projects in the future, will allow for on-going maintenance and rehabilitation to extend the effective useful life of the thirty lift stations, and prevent the likelihood of failure requiring emergency repairs. In addition, consideration will be taken to elevate controls for facilities in flood-prone locations, and to add back-up power systems at strategic locations to ensure for continued service during power outages. Budget costs are based upon costs required for recent rehabilitation of other lift stations in the system.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		As Needed		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		As Needed		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS								
Final Proposal Docs:		As Needed		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R								
Proposals/Bids Received:		As Needed		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		As Needed			<input type="checkbox"/> OTHER								
Substantial Completion:		As Needed											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 111,000	\$ -	\$ 8,000	\$ 8,000	\$ 10,000	\$ 10,000	\$ 12,500	\$ 12,500	\$ 12,500	\$ 12,500	\$ 12,500	\$ 12,500	
Construction	\$ 1,828,000	\$ 700,000	\$ 84,000	\$ 84,000	\$ 105,000	\$ 105,000	\$ 125,000	\$ 125,000	\$ 125,000	\$ 125,000	\$ 125,000	\$ 125,000	
CPS, CM&I, and CMT	\$ 111,000	\$ -	\$ 8,000	\$ 8,000	\$ 10,000	\$ 10,000	\$ 12,500	\$ 12,500	\$ 12,500	\$ 12,500	\$ 12,500	\$ 12,500	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 2,050,000	\$ 700,000	\$ 100,000	\$ 100,000	\$ 125,000	\$ 125,000	\$ 150,000	\$ 150,000	\$ 150,000	\$ 150,000	\$ 150,000	\$ 150,000	

*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR		DIVISION					
South Shore Gravity Main Rehabilitation				WW21GR		2021-2027		The Woodlands					
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>Some wastewater lines within the collection system have been in service for over 40 years. The aging system requires rehabilitation to avoid collection system failure, sewage overflows, and permit violations. Through the Asset Management Program and the Sanitary Sewer Transmission Assessment and Renewal (SSTAR) Program, specific line segments were identified as high risk for failure and should be replaced or rehabilitated in the near term.</p> <p>The SSTAR Program conducted in 2019 and 2020 included a condition assessment consisting of closed circuit television (CCTV) inspection and analysis of expected remaining useful life. CCTV video footage showed significant deterioration of the existing gravity mains, requiring rehabilitation or replacement. Additionally, these line segments were scored with a high consequence of failure, due to their location, difficulties with access, and their criticality.</p> <p>This project proposes to renew approximately 9,800 linear feet of existing sanitary sewer gravity mains varying in size from 15-inch to 42-inch, by the cured-in-place pipe (CIPP) pipe lining method, as well as television inspection, bypass pumping to maintain sewer flows during construction, rehabilitation of manholes along the sanitary sewer alignment, service reconnections by remote, and mechanical cleaning if needed.</p> <p>Active communication with the residents of the affected west lake area, as well as the golf course, to coordinate and schedule the necessary work and routing of bypass pump piping is ongoing.</p> <p>Rehabilitation costs are from updated costs from February 2025.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		Completed		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		Completed		<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS								
Final Proposal Docs:		FY 2025 - Q3		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R								
Proposals/Bids Received:		FY 2025 - Q4		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		FY 2026 - Q1			<input type="checkbox"/> OTHER								
Substantial Completion:		FY 2027 - Q3											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 213,888	\$ 213,888	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 640,433	\$ 640,433	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 10,955,000	\$ -	\$ 7,231,000	\$ 3,724,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 1,095,000	\$ -	\$ 723,000	\$ 372,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Property Cost	\$ 5,000	\$ 5,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Land Acquisition Team	\$ 45,000	\$ 45,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total**	\$ 12,954,321	\$ 904,321	\$ 7,954,000	\$ 4,096,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	


*Budget includes 30% contingency, and 3% inflation per year.

**\$263,888 is R&R Funds; \$12,690,433 is 2017 Bond Funds

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION					
Wastewater Owner's Advisor				WWF10A		2024-TBD			The Woodlands					
PROJECT DESCRIPTION						PROJECT MAP/PICTURE								
<p>The existing wastewater infrastructure in The Woodlands is aging with certain treatment and conveyance components expected to reach the end of their useful life in the coming decade. Improvements must be made, and actions must be taken to maintain the level of service (LoS) expected by San Jacinto River Authority (SJRA) customers. In March 2023, SJRA completed the initial phase of The Woodlands Wastewater Strategic Plan, which laid out a phased approach to maintaining the desired level of service in The Woodlands. The report also defined a project to replace the aging infrastructure of Wastewater Treatment Facility (WWTF) No. 1. In January 2024, SJRA completed a Facility Master Plan for a new Water Reclamation Facility (WRF) to be located at and adjacent to the existing WWTF No. 1. The current proposed average annual daily flow capacity for the new facility is 7.0 million gallons per day (MGD) with a wet weather peak flow of 18 MGD. The facility master plan was based around a Membrane Bioreactor (MBR) treatment process.</p> <p>An additional study is currently being completed by the Wastewater Owner's Advisor to compare additional short-listed alternatives for renewal/replacement of WWTF No. 1. SJRA will continue to coordinate with the MUD Boards to determine the best valued renewal/replacement alternative for WWTF No. 1 to move forward with.</p> <p>The required funding shown below is based on project estimates developed during the Facility Master Plan and will be adjusted pending outcome of the additional WWTF No. 1 study. Future Owner's Advisor Service may include, but are not limited to, project management and controls activities, procurement support, development of design standards, and support during design, construction, and start-up the recommended improvements for WWTF No. 1.</p>														
PROJECT SCHEDULE				DELIVERY	FUNDING									
Initiate Cons. Selection:		Completed		<input type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:		Completed		<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS									
Final Proposal Docs:		TBD		<input checked="" type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R									
Proposals/Bids Received:		TBD		<input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		TBD			<input type="checkbox"/> OTHER									
Substantial Completion:		TBD												
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035		
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Engineering/Design	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Construction	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
CPS, CM&I, and CMT	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Owner's Advisor**	\$ 14,996,096	\$ 834,096	\$ 1,810,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,162,000	\$ -	\$ -	\$ -		
Total	\$ 14,996,096	\$ 834,096	\$ 1,810,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,162,000	\$ -	\$ -	\$ -		


*Budget includes 30% contingency, and 3% inflation per year.

** Total Bond Funded portion = \$14,162,000. Total R&R Funded Portion = \$834,096.


PROJECT NAME				PROJECT ID		FISCAL YEAR		DIVISION					
Lift Station No. 1 Gravity Main Bypass and Decommissioning				WWLS1B		2023-2026		The Woodlands					
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>Lift Station No. 1 was constructed in 1974 to receive wastewater flows from areas along Grogan's Mill Road north of Woodlands Parkway and pump these flows to Wastewater Treatment Facility No. 1. Recent evaluation of the force main, also constructed in 1974, found it to be in poor condition, and in need of replacement. In the mid-1990s, a 42-inch gravity line was constructed approximately 1,400 LF to the west of the lift station, which a feasibility study performed in 2023 found to be at a depth and adequate size to intercept the flows going to Lift Station No. 1. Constructing a gravity main along the north side of Woodlands Parkway from just upstream of the lift station to the 42-inch gravity main would allow the lift station to be cut below grade, gutted and filled and the force main grout-filled and capped, and therefore, eliminate further lift station life cycle operation and maintenance costs for 50-year old infrastructure. The existing 18-inch gravity line receiving flow from Lift Station No. 1's force main will also need to be decommissioned and abandoned.</p> <p>A feasibility study and preliminary engineering have been completed on this project, and final design is underway. The budget costs were derived from the preliminary engineering phase by the design consultant. Final detailed engineering design is currently in progress and the construction cost shown below is an estimate based on assumptions made by the consultant during preliminary engineering with a general understanding of the area. The construction of this project will be funded utilizing bond funds received from the Texas Water Development Board.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		Completed		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		Completed		<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS								
Final Proposal Docs:		FY 2025 - Q3		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R								
Proposals/Bids Received:		FY 2025 - Q4		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		FY 2026 - Q1			<input type="checkbox"/> OTHER								
Substantial Completion:		FY 2026 - Q4											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 23,711	\$ 23,711	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 194,000	\$ 184,000	\$ 10,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 4,000,000	\$ -	\$ 4,000,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 150,000	\$ -	\$ 150,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Land Acquisition	\$ 20,000	\$ -	\$ 20,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 4,387,711	\$ 207,711	\$ 4,180,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	

*Budget includes 30% contingency, and 3% inflation per year.

**Total Bond Funded portion = \$4,000,000. Total R&R Funded Portion = \$387,711

PROJECT NAME				PROJECT ID	FISCAL YEAR			DIVISION					
WWTF No. 2 Grit Classifier Improvements				WWP2GC	2025-2026			The Woodlands					
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>The grit classifier at Wastewater Treatment Facility No. 2 is utilized to separate heavier grit from lighter organic material and the carrier water from the primary grit removal system. A grit classifier consists of a clarifying hopper to allow heavier grit to settle while lighter organic material leaves the hopper by overflow and is returned to the main process stream for further treatment. The heavier grit is then removed from the system via a slow-moving screw and discharged into a dumpster. The current grit classifier was installed in 2017; however, this classifier was originally installed at Wastewater Treatment Facility No. 1 in 2009 but was moved following the construction of a new grit system. Unfortunately, the design and size of this classifier is insufficient and a new, properly sized classifier should be installed. Also, the grit pump piping from the grit pumps to the classifier regularly clogs due to the length and numerous bends in the piping.</p> <p>The new grit classifier is proposed to be installed at a different location which is closer to the grit pumps, therefore allowing for much less piping and bends, which should eliminate the clogging issue. To do so, a new concrete access driveway will be built to the new location, an awning will be constructed to shelter the dumpster, and drainage installed.</p> <p>Final design was initiated for this project in September 2024, and construction will commence in FY2026.</p>													
PROJECT SCHEDULE			DELIVERY	FUNDING									
Initiate Cons. Selection:		Completed	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:		Completed	<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS									
Final Proposal Docs:		FY 2025 - Q3	<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R									
Proposals/Bids Received:		FY 2025 - Q3	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		FY 2026 - Q1		<input type="checkbox"/> OTHER									
Substantial Completion:		FY 2026 - Q4		Excess Funds									
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 97,000	\$ 97,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 1,036,000	\$ -	\$ 1,036,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 52,000	\$ -	\$ 52,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 1,185,000	\$ 97,000	\$ 1,088,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	

*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
WWTF No. 2 Tertiary Filter Improvements (2nd and 3rd Filter)				WW02FR		2021-2027			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>Wastewater Treatment Facility (WWTF) No. 2 utilizes tertiary filters to treat effluent prior to disinfection. Filters 1 and 2 are sand filters, while Filter 3 was replaced with a new cloth media filter in 2016. The current sand filters are rated for 2 MG of flow each, with the one installed cloth media filter rated for 6 MG of flow. The TCEQ discharge permit allows for 15.6 MG of flow during a rain event, of which only 10.0 MG is able to be treated with the current filters.</p> <p>Existing sand filters 1 and 2 have been in service since 2006, have a service life of 15-25 years, are rated for 2 MG each, and have experienced performance issues which limit wastewater flows through WWTF No. 2. This project will replace the remaining two sand filters with cloth media filters which will eliminate the performance issues and allow all flow during a rain event to pass through the filters.</p> <p>An evaluation was conducted in 2021 to determine the capital and O&M cost of replacing the existing unit with a similar unit versus a modification to a newer technology (cloth media). To replace the existing unit with a similar unit, capital and O&M costs were \$106.85/MG and \$27.40, respectively. The capital and O&M cost to modify to cloth media is \$41.76/MG and \$7.99/MG, respectively.</p> <p>Costs are based on an design that was done in 2021 and updated recently with a current engineer's estimate (December 2024). Construction will be funded from 2017 TWDB Wastewater Bonds, whereas the remaining engineering, CMT, etc. will be paid from R&R funds.</p>													
PROJECT SCHEDULE				DELIVERY		FUNDING							
Initiate Cons. Selection:		Completed		<input checked="" type="checkbox"/> CSP		<input type="checkbox"/> O&M							
PSA/WO Issued:		Completed		<input type="checkbox"/> QUOTES		<input checked="" type="checkbox"/> BONDS							
Final Proposal Docs:		Completed		<input type="checkbox"/> PROFESSIONAL		<input checked="" type="checkbox"/> R&R							
Proposals/Bids Received:		Completed		<input type="checkbox"/> OTHER		<input type="checkbox"/> GRANTS							
Constr. Contract to Board:		FY 2025 - Q3				<input type="checkbox"/> OTHER							
Substantial Completion:		FY 2027 - Q1											
BUDGET*		TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035
Planning/Permitting/PER*		\$ 100,000	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Engineering/Design**		\$ 276,118	\$ 276,118	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction		\$ 5,366,000	\$ 500,000	\$ 4,492,000	\$ 374,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
CPS, CM&I, and CMT**		\$ 159,209	\$ 59,209	\$ 92,000	\$ 8,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Land Acquisition		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Equipment Purchase		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total		\$ 5,901,327	\$ 935,327	\$ 4,584,000	\$ 382,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -

*Budget includes 0% contingency, and 0% inflation per year.



**Total Bond Funded Portion = \$5,366,000. Total R&R Funded Portion = \$535,327.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION					
Wastewater System Land Acquisition				WWF1LA		2024-TBD			The Woodlands					
PROJECT DESCRIPTION						PROJECT MAP/PICTURE								
<p>Through the Wastewater Strategic Planning efforts, the MUDs voted to move forward with further investigations into replacement of Wastewater Treatment Facility (WWTF) No. 1 with Water Reclamation Facility (WRF) No. 1, including the purchasing of adjacent land. The proposed facility will require the acquisition of new fee property and potential easements from land owners to construct, operate and maintain the new wastewater treatment facility.</p> <p>Additionally, through the Wastewater Strategic Planning efforts, an option to construct a new gravity main was explored. The proposed new gravity main will provide for the reliable, long term conveyance of wastewater to WWTF No. 1. The new conveyance system will require the acquisition of new fee property and additional easements from land owners to construct, operate, and maintain the new proposed conveyance infrastructure near/adjacent to WWTF No. 1.</p> <p>For this project, the parcel areas outlined in blue on the picture are the proposed parcels to acquire for the new treatment facility and conveyance system near/adjacent to WWTF No. 1. This project does not include additional land acquisition that may be required along the full alignment of the new conveyance gravity main route off-site. This project includes a budget for property research, survey, appraisals, legal services, purchase costs, and other expenditures associated with acquiring the property rights and easements. This project is currently on hold and will be adjusted pending the outcome of a study currently underway for WWTF No. 1 renewal/replacement and the conveyance optimization routing study.</p>														
PROJECT SCHEDULE				DELIVERY	FUNDING									
Initiate Cons. Selection: Completed				<input type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued: FY 2024 - Q1				<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS									
Final Proposal Docs: N/A				<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R									
Proposals/Bids Received: N/A				<input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board: N/A					<input type="checkbox"/> OTHER									
Substantial Completion: N/A														
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035		
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Engineering/Design	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Construction	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
CPS, CM&I, and CMT	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Land Acquisition Team	\$ 1,202,000	\$ 260,000	\$ 471,000	\$ 471,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Property Cost	\$ 8,598,000	\$ -	\$ 4,299,000	\$ 4,299,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Total	\$ 9,800,000	\$ 260,000	\$ 4,770,000	\$ 4,770,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		

*Budget includes 30% contingency, and 3% inflation per year.


PROJECT NAME					PROJECT ID	FISCAL YEAR			DIVISION																			
Lift Station No. 21 Force Main Renewal					WWFM21	2026 - 2027			The Woodlands																			
PROJECT DESCRIPTION					PROJECT MAP/PICTURE																							
<p>Some parts of the existing wastewater system, specifically the force main serving Lift Station No. 21, have been in service for over 40 years. The aging system requires renewal to avoid collection system failure. Through the Asset Management Program and site specific condition assessments, specific force mains were identified as high risk for failure and were evaluated for rehabilitation or replacement. A force main condition assessment was conducted in June 2022 that included a records analysis, televising of the force main and a physical inspection to determine estimated remaining useful life of each force main. The resulting data was compiled for Lift Station No. 21's force main:</p> <table><tr><td></td><td></td><td>Original</td><td>Current</td><td>Linear</td></tr><tr><td>Lift station</td><td>Installed</td><td>Thickness (in.)</td><td>Thickness (in.)</td><td>Footage (ft)</td></tr><tr><td>No. 21</td><td>1982</td><td>0.34</td><td>0.10</td><td>2,600</td></tr></table> <p>The results show that the force main has lost approximately 70% of its original thickness and is at high risk of structural collapse. Therefore, the force main will require rehabilitation or replacement. An initial study of various rehabilitation and replacements methods will occur to find the best value option for renewal.</p> <p>The estimated construction cost budget is based upon preliminary quotes from third party vendors for different renewal methods.</p>							Original	Current	Linear	Lift station	Installed	Thickness (in.)	Thickness (in.)	Footage (ft)	No. 21	1982	0.34	0.10	2,600									
		Original	Current	Linear																								
Lift station	Installed	Thickness (in.)	Thickness (in.)	Footage (ft)																								
No. 21	1982	0.34	0.10	2,600																								
PROJECT SCHEDULE				DELIVERY	FUNDING																							
Initiate Cons. Selection:				FY 2025 - Q4	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M																						
PSA/WO Issued:				FY 2026 - Q1	<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS																						
Final Proposal Docs:				FY 2026 - Q4	<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R																						
Proposals/Bids Received:				FY 2026 - Q4	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS																						
Constr. Contract to Board:				FY 2027 - Q1		<input type="checkbox"/> OTHER																						
Substantial Completion:				FY 2027 - Q4																								
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035																
Planning/Permitting/PER	\$ 47,000	\$ -	\$ 47,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -																
Engineering/Design	\$ 47,000	\$ -	\$ 47,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -																
Construction	\$ 483,000	\$ -	\$ -	\$ 483,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -																
CPS, CM&I, and CMT	\$ 48,000	\$ -	\$ -	\$ 48,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -																
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -																
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -																
Total	\$ 625,000	\$ -	\$ 94,000	\$ 531,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -																

*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID	FISCAL YEAR	DIVISION						
Lift Station 24 Improvements				WWLS24	2026-2028	The Woodlands						
PROJECT DESCRIPTION					PROJECT MAP/PICTURE							
<p>The current Lift Station No. 24 site includes two wet well lift stations (Lift Station No. 24A installed in 1999; Lift Station No. 24B installed in 2004), and a control/generator building. During Hurricane Harvey in 2017, the entire site flooded with a water depth of approximately 4 feet. In 2024, Federal Community Project funds become available to allow for reconfiguration of the site to mitigate the effects of future flooding. These improvements include the construction of a new control/generator building/platform at a higher elevation, and the abandonment of the older, smaller wet well lift station and diversion of flow into the newer, larger wet well lift station. It has been confirmed the newer, larger lift station can accommodate the added flows.</p> <p>Pricing utilized for the budget was from a previous lift station replacement project as well as pricing for a building. The existing generator can be re-used. It is anticipated that approximately \$1.825MM of the cost will be through Federal Community Project funds.</p>												
PROJECT SCHEDULE				DELIVERY	FUNDING							
Initiate Cons. Selection:	FY 2025 - Q3		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:	FY 2025 - Q4		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS								
Final Proposal Docs:	FY 2027 - Q1		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R								
Proposals/Bids Received:	FY 2027 - Q2		<input type="checkbox"/> OTHER	<input checked="" type="checkbox"/> GRANTS								
Constr. Contract to Board:	FY 2027 - Q2			<input type="checkbox"/> OTHER								
Substantial Completion:	FY 2028 - Q2			Federal Funds								
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035
Planning/Permitting/PER	\$ 353,000	\$ -	\$ 232,400	\$ 61,200	\$ 59,400	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Engineering/Design	\$ 173,000	\$ -	\$ 51,900	\$ 121,100	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction	\$ 1,734,000	\$ -	\$ -	\$ 867,000	\$ 867,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
CPS, CM&I, and CMT	\$ 173,000	\$ -	\$ -	\$ 86,500	\$ 86,500	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total	\$ 2,433,000	\$ -	\$ 284,300	\$ 1,135,800	\$ 1,012,900	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -

*Budget includes 30% contingency, and 3% inflation per year.



**\$1,825,000 of total from Federal Funds.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
Wastewater Treatment Facility No. 3 Bar Screen Replacement				WWP3BS		2027			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>In 2003, the original WWTF No. 3 package plant was replaced with a 0.90 MGD conventional wastewater facility with mechanical screening achieved by a Huber Step Screen bar screen. Due to failures, the Huber Step Screen was replaced in 2012 with a Parkson Perforated Screen, and after an extensive mechanical failure in 2021 the Parkson Perforated Screen was replaced with a Huber Rake Max bar screen originally designed for and installed at WWTF No. 2. This bar screen experienced a extensive mechanical failure in November 2024, resulting in a bent frame, the chain and internal gearing. This failure was a result of binding of internal mechanical parts, not large debris. The screen has been repaired to allow for operation; however, due to the failure that occurred to the frame, the bar screen has a reduced service life. Additionally, the Huber Rake Max was not designed for WWTF No. 3 since it was originally designed for an installed at WWTF No. 2.</p> <p>This project is to purchase and install a new mechanical bar screen that will replace the current bar screen but will be designed specifically for operation at WWTF No. 3. The new mechanical screening equipment will be installed in-house by SJRA.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection: FY 2027				<input type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued: FY 2027				<input checked="" type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS								
Final Proposal Docs: FY 2027				<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R								
Proposals/Bids Received: FY 2027				<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board: FY 2027					<input type="checkbox"/> OTHER								
Substantial Completion: FY 2027													
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 10,000	\$ -	\$ -	\$ 10,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 10,000	\$ -	\$ -	\$ 10,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ 200,000	\$ -	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 220,000	\$ -	\$ -	\$ 220,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	



*Budget includes 10% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID	FISCAL YEAR	DIVISION																					
Lift Station No. 13 Force Main Renewal				WW13FM	2027-2028	The Woodlands																					
PROJECT DESCRIPTION				PROJECT MAP/PICTURE																							
<p>Some parts of the existing wastewater system, specifically the force main for Lift Station No. 13, have been in service for over 40 years. The aging system requires renewal to avoid collection system failure. Through the Asset Management Program and site specific condition assessments, specific force mains were identified as high risk for failure and were evaluated for rehabilitation or replacement. A force main condition assessment was conducted in June 2022 that included a records analysis, televising of the force main and a physical inspection to determine estimated remaining useful life of each force main. The resulting data was compiled for Lift Station No. 13's force main:</p> <table><tr><td></td><td>Original</td><td>Current</td><td>Linear</td></tr><tr><td>Lift station</td><td>Installed</td><td>Thickness (in.)</td><td>Thickness (in.)</td><td>Footage (ft)</td></tr><tr><td>No. 13</td><td>1983</td><td>0.36</td><td>0.10</td><td>2,500</td></tr></table> <p>The results show that the force main has lost approximately 70% of its original thickness and is at high risk of structural collapse. Therefore, the force main will require rehabilitation or replacement. An initial study of various rehabilitation and replacements methods will occur to find the best value option for renewal.</p> <p>The estimated construction cost budget is based upon preliminary quotes from third party vendors for different renewal methods.</p>					Original	Current	Linear	Lift station	Installed	Thickness (in.)	Thickness (in.)	Footage (ft)	No. 13	1983	0.36	0.10	2,500										
	Original	Current	Linear																								
Lift station	Installed	Thickness (in.)	Thickness (in.)	Footage (ft)																							
No. 13	1983	0.36	0.10	2,500																							
PROJECT SCHEDULE				DELIVERY	FUNDING																						
Initiate Cons. Selection:		FY 2026 - Q4	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M																							
PSA/WO Issued:		FY 2027 - Q1	<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS																							
Final Proposal Docs:		FY 2027 - Q4	<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R																							
Proposals/Bids Received:		FY 2027 - Q4	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS																							
Constr. Contract to Board:		FY 2028 - Q1		<input type="checkbox"/> OTHER																							
Substantial Completion:		FY 2028 - Q4																									
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035															
Planning/Permitting/PER	\$ 83,000	\$ -	\$ -	\$ 83,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -															
Engineering/Design	\$ 83,000	\$ -	\$ -	\$ 83,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -															
Construction	\$ 852,000	\$ -	\$ -	\$ -	\$ 852,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -															
CPS, CM&I, and CMT	\$ 85,000	\$ -	\$ -	\$ -	\$ 85,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -															
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -															
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -															
Total	\$ 1,103,000	\$ -	\$ -	\$ 166,000	\$ 937,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -															




*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
WWTF No. 2 Belt Press and Conveyor Replacement				WW2SCR		2027-2030			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>Wastewater Treatment Facility (WWTF) No. 2 includes a 1.5 meter wide belt press and sludge conveyor system, installed in 1997. Additionally, in 2003 a 2.0 meter wide belt press was installed. These belt filter presses and the conveyor are experiencing recurring mechanical issues which require more frequent repairs. These issues and repairs include inoperable and/or leaking belt press pump, belts that require more frequent replacement, polymer piping breaks, and inoperable flow meters. Replacing both belt presses with modern technology is expected to increase the percentage of solids production, decrease the chemical costs, and decrease overall operation and maintenance costs. The metal building will also be replaced as structural members and sheathing are corroding due to the humid and corrosive environment.</p> <p>The current conveyor system is steep and has required modification since its installation to reduce potential safety issues. The current belt-type conveyor system is proposed to be replaced with a screw-type conveyance system. The screw-type conveyor is in an enclosed unit, which will prevent spillage of dewatered sludge onto the floor, minimizing the need for regular cleaning and potential water contamination.</p> <p>Costs for this project were estimated based upon a previous belt press facility constructed at WWTF No. 1, as well as condition assessment and capacity studies in 2016 and 2022. The improved dewatering at the new facility created a cost savings from both sludge disposal and polymer usage costs.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:	FY 2027	<input checked="" type="checkbox"/>	CSP	<input type="checkbox"/>	O&M								
PSA/WO Issued:	FY 2027	<input type="checkbox"/>	QUOTES	<input type="checkbox"/>	BONDS								
Final Proposal Docs:	FY 2027	<input type="checkbox"/>	PROFESSIONAL	<input checked="" type="checkbox"/>	R&R								
Proposals/Bids Received:	FY 2027	<input type="checkbox"/>	OTHER	<input type="checkbox"/>	GRANTS								
Constr. Contract to Board:	FY 2028			<input type="checkbox"/>	OTHER								
Substantial Completion:	FY 2030												
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 611,000	\$ -	\$ -	\$ 611,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 625,000	\$ -	\$ -	\$ 122,000	\$ 503,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 6,482,000	\$ -	\$ -	\$ -	\$ 1,573,000	\$ 3,240,000	\$ 1,669,000	\$ -	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 648,000	\$ -	\$ -	\$ -	\$ 157,000	\$ 324,000	\$ 167,000	\$ -	\$ -	\$ -	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 8,366,000	\$ -	\$ -	\$ 733,000	\$ 2,233,000	\$ 3,564,000	\$ 1,836,000	\$ -	\$ -	\$ -	\$ -	\$ -	



*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION																													
Forcemain Renewal				WW22FM		2022-2027			The Woodlands																													
PROJECT DESCRIPTION						PROJECT MAP/PICTURE																																
<p>Some parts of the existing wastewater system, specifically the force mains serving the lift stations listed below, have been in service for over 40 years. The aging system requires renewal to avoid collection system failure. Through the Asset Management Program and site specific condition assessments, specific force mains were identified as high risk for failure and were evaluated for rehabilitation or replacement. A force main condition assessment was conducted in June 2022 that included a records analysis, televising of the force main and a physical inspection to determine estimated remaining useful life of each force main.</p> <p>Based on the information above and the service life of concrete lined ductile iron pipe (40-50 years), a list of lift station force mains needing repair was established. Costs were determined based upon recent force main line replacement costs for the certain pipe diameter and multiplied by the length to be replaced. Based on the condition assessment, sections of the force main that showed corrosion will be replaced.</p> <table><thead><tr><th>Lift station</th><th>Installed</th><th><u>Original Thickness (in.)</u></th><th><u>Current Thickness (in.)</u></th></tr></thead><tbody><tr><td>No. 7</td><td>1979</td><td>0.47</td><td>0.43</td></tr><tr><td>No. 11</td><td>1982</td><td>0.36</td><td>0.31</td></tr><tr><td>No. 10</td><td>1980</td><td>0.46</td><td>0.38</td></tr><tr><td>No. 9</td><td>1981</td><td>0.46</td><td>0.45</td></tr><tr><td>No. 19</td><td>1982</td><td>0.32</td><td>0.31</td></tr></tbody></table>						Lift station	Installed	<u>Original Thickness (in.)</u>	<u>Current Thickness (in.)</u>	No. 7	1979	0.47	0.43	No. 11	1982	0.36	0.31	No. 10	1980	0.46	0.38	No. 9	1981	0.46	0.45	No. 19	1982	0.32	0.31									
						Lift station	Installed	<u>Original Thickness (in.)</u>	<u>Current Thickness (in.)</u>																													
No. 7	1979	0.47	0.43																																			
No. 11	1982	0.36	0.31																																			
No. 10	1980	0.46	0.38																																			
No. 9	1981	0.46	0.45																																			
No. 19	1982	0.32	0.31																																			
PROJECT SCHEDULE				DELIVERY	FUNDING																																	
Initiate Cons. Selection:		As Needed		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M																																	
PSA/WO Issued:		As Needed		<input checked="" type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS																																	
Final Proposal Docs:		As Needed		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R																																	
Proposals/Bids Received:		As Needed		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS																																	
Constr. Contract to Board:		As Needed			<input type="checkbox"/> OTHER																																	
Substantial Completion:		As Needed																																				
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035																										
Planning/Permitting/PER	\$ 86,269	\$ 86,269	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -																										
Engineering/Design	\$ 112,000	\$ -	\$ -	\$ -	\$ -	\$ 15,000	\$ 15,000	\$ 16,000	\$ 16,000	\$ 16,000	\$ 17,000	\$ 17,000																										
Construction	\$ 1,122,000	\$ -	\$ -	\$ -	\$ -	\$ 146,000	\$ 151,000	\$ 155,000	\$ 160,000	\$ 165,000	\$ 170,000	\$ 175,000																										
CPS, CM&I, and CMT	\$ 112,000	\$ -	\$ -	\$ -	\$ -	\$ 15,000	\$ 15,000	\$ 16,000	\$ 16,000	\$ 16,000	\$ 17,000	\$ 17,000																										
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -																										
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -																										
Total	\$ 1,432,269	\$ 86,269	\$ -	\$ -	\$ -	\$ 176,000	\$ 181,000	\$ 187,000	\$ 192,000	\$ 197,000	\$ 204,000	\$ 209,000																										


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
WWTF No. 2 Clarifier Rehabilitation				WW02CR		2031-2032			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>Two clarifiers at Wastewater Treatment Facility (WWTF) No. 2 were installed in 1995, and one clarifier was installed in 2003. The existing metal components are beginning to show signs of corrosion, however, the corrosion is currently being monitored and temporarily mitigated with patch repairs. The mechanical equipment in all three clarifiers is still in usable condition but is beyond or reaching the end of their useful life (20 years). Therefore, it is recommended to replace this metal and mechanical equipment prior to failure at all three clarifiers. SJRA will continue to monitor the condition of the clarifier components, and will adjust the project schedule accordingly.</p> <p>The project includes replacement of the mechanical components of Clarifier Nos. 1, 2 and 3 including clarifier mechanisms, weirs and baffles, weir cleaning brushes, electrical, and instrumentation. This includes replacement of single skimmer arms with dual skimmer arms, and replacement of the Clarifier No. 3 stilling well.</p> <p>Costs are estimated using previous clarifier rehabilitation pricing and recent mechanical equipment pricing.</p>						 							
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		FY 2030	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:		FY 2031	<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS									
Final Proposal Docs:		FY 2031	<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R									
Proposals/Bids Received:		FY 2031	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		FY 2031		<input type="checkbox"/> OTHER									
Substantial Completion:		FY 2032											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 163,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 163,000	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 1,680,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,680,000	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 168,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 168,000	\$ -	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 2,011,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 163,000	\$ 1,848,000	\$ -	\$ -	\$ -	


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR		DIVISION				
WWTF No. 2 Basin Coating				WWP2BC		2031-2033		The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE						
<p>Wastewater Treatment Facility No. 2 was primarily constructed in two phases, with Phase I occurring in 1995 and Phase II occurring in 2003. Long-term exposure to corrosive gas in the wastewater facility will degrade the concrete structures over-time. The basins at Wastewater Treatment Facility No. 2 exposed to the most corrosive gases are the aeration basins, digester, and thickener. To remedy any damage and prevent further concrete degradation and maintain service life, the basins will be coated with a material which will provide additional structural integrity as well as protect the concrete from further degradation over time.</p> <p>Costs for this project were estimated based upon the approximate surface area of the various structures to be coated in the project and multiplying by coating pricing (with inflation to the years of this project) from recent projects at other SJRA facilities.</p>												
PROJECT SCHEDULE				DELIVERY	FUNDING							
Initiate Cons. Selection: FY 2031				<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M							
PSA/WO Issued: FY 2031				<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS							
Final Proposal Docs: FY 2032				<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R							
Proposals/Bids Received: FY 2032				<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS							
Constr. Contract to Board: FY 2032					<input type="checkbox"/> OTHER							
Substantial Completion: FY 2033												
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Engineering/Design	\$ 325,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 160,000	\$ 165,000	\$ -	\$ -	\$ -
Construction	\$ 3,343,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,647,000	\$ 1,696,000	\$ -	\$ -
CPS, CM&I, and CMT	\$ 335,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 165,000	\$ 170,000	\$ -	\$ -
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total	\$ 4,003,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 160,000	\$ 1,977,000	\$ 1,866,000	\$ -	\$ -


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
WWTF No. 2 Blower Replacement				WWP2BR		2032-2034			The Woodlands				
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>Phase I of Wastewater Treatment Facility No. 2 was constructed in 1995. The blowers for the aeration basins and the post-aeration blowers at the filter basin are original to the 1995 construction and are reaching the end of their useful life. However, SJRA will continue to monitor the condition of the blowers and will adjust their replacement schedule accordingly. When replaced, the blowers are planned to be replaced with high-efficiency positive displacement blowers of equal capacity. The size of the blowers at the aeration basin will be increased from 150 hp to 200 hp.</p> <p>Costs were estimated based upon previous studies for condition assessment at Wastewater Treatment Facility No. 2 in 2016 and 2022, as well as estimates for similar blower replacement at Wastewater Treatment Facility No. 1.</p>													
PROJECT SCHEDULE			DELIVERY	FUNDING									
Initiate Cons. Selection:	FY 2032	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M										
PSA/WO Issued:	FY 2032	<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS										
Final Proposal Docs:	FY 2032	<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R										
Proposals/Bids Received:	FY 2033	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS										
Constr. Contract to Board:	FY 2033		<input type="checkbox"/> OTHER										
Substantial Completion:	FY 2034												
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 387,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 387,000	\$ -	\$ -	\$ -	
Engineering/Design	\$ 394,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 194,000	\$ 200,000	\$ -	\$ -	
Construction	\$ 4,042,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,295,000	\$ 1,747,000	\$ -	
CPS, CM&I, and CMT	\$ 404,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 229,000	\$ 175,000	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 5,227,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 581,000	\$ 2,724,000	\$ 1,922,000	\$ -	

*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION				
WWTF No. 3 Clarifier Rehabilitation				WW03CR		2034-2035			The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>The two clarifiers at Wastewater Treatment Facility (WWTF) No. 3 were installed in 2001. The existing metal components are beginning to show signs of corrosion, however, the corrosion is currently being monitored and temporarily mitigated with patch repairs. The mechanical equipment is still operational but is beyond the end of its expected useful life (20 years). Therefore, it is recommended to plan to replace the mechanical and metal equipment in both clarifiers. SJRA will continue to monitor the condition of the clarifier components, and will adjust the project schedule accordingly.</p> <p>The project includes replacement of the mechanical components of Clarifier Nos. 1 and 2 including clarifier mechanisms, weirs and baffles, weir cleaning brushes, electrical, and instrumentation.</p> <p>Costs are estimated using previous clarifier rehabilitation pricing and recent mechanical equipment pricing.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		FY 2034		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		FY 2034		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS								
Final Proposal Docs:		FY 2034		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R								
Proposals/Bids Received:		FY 2034		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		FY 2034			<input type="checkbox"/> OTHER								
Substantial Completion:		FY 2035											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 85,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 85,000	\$ -	
Construction	\$ 874,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 874,000	
CPS, CM&I, and CMT	\$ 87,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 87,000	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 1,046,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 85,000	\$ 961,000	

*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR		DIVISION				
WWTF No. 3 Blower Replacement				WWP3BR		2035-2036		The Woodlands				
PROJECT DESCRIPTION						PROJECT MAP/PICTURE						
<p>Three of the four blowers for the aeration basins and digester basins were installed as part of the facility construction completed in 2001. The fourth blower was installed in 2024. These three blowers installed are reaching the end of their useful life. However, SJRA will continue to monitor the condition of the blowers and will adjust their replacement schedule accordingly. When replaced, the blowers are planned to be replaced with high-efficiency positive displacement blowers of equal capacity.</p> <p>Costs were estimated based estimates from studies performed for Wastewater Treatment Facility Nos. 1 and 2.</p>												
PROJECT SCHEDULE				DELIVERY	FUNDING							
Initiate Cons. Selection:		FY 2035		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M							
PSA/WO Issued:		FY 2035		<input type="checkbox"/> QUOTES	<input type="checkbox"/> BONDS							
Final Proposal Docs:		FY 2035		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R							
Proposals/Bids Received:		FY 2035		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS							
Constr. Contract to Board:		FY 2036			<input type="checkbox"/> OTHER							
Substantial Completion:		FY 2036										
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035
Planning/Permitting/PER	\$ 175,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 175,000
Engineering/Design	\$ 175,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 175,000
Construction	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
CPS, CM&I, and CMT	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total	\$ 350,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 350,000


*Budget includes 30% contingency, and 3% inflation per year.

** Project continues into FY 2036. Total project is approximately \$2,333,000.

PROJECT NAME				PROJECT ID	FISCAL YEAR	DIVISION							
Wastewater Owner's Advisor				WWF10A	2024-TBD	The Woodlands							
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>The existing wastewater infrastructure in The Woodlands is aging with certain treatment and conveyance components expected to reach the end of their useful life in the coming decade. Improvements must be made, and actions must be taken to maintain the level of service (LoS) expected by San Jacinto River Authority (SJRA) customers. In March 2023, SJRA completed the initial phase of The Woodlands Wastewater Strategic Plan, which laid out a phased approach to maintaining the desired level of service in The Woodlands. The report also defined a project to replace the aging infrastructure of Wastewater Treatment Facility (WWTF) No. 1. In January 2024, SJRA completed a Facility Master Plan for a new Water Reclamation Facility (WRF) to be located at and adjacent to the existing WWTF No. 1. The current proposed average annual daily flow capacity for the new facility is 7.0 million gallons per day (MGD) with a wet weather peak flow of 18 MGD. The facility master plan was based around a Membrane Bioreactor (MBR) treatment process.</p> <p>An additional study is currently being completed by the Wastewater Owner's Advisor to compare additional short-listed alternatives for renewal/replacement of WWTF No. 1. SJRA will continue to coordinate with the MUD Boards to determine the best valued renewal/replacement alternative for WWTF No. 1 to move forward with.</p> <p>The required funding shown below is based on project estimates developed during the Facility Master Plan and will be adjusted pending outcome of the additional WWTF No. 1 study. Future Owner's Advisor Service may include, but are not limited to, project management and controls activities, procurement support, development of design standards, and support during design, construction, and start-up the recommended improvements for WWTF No. 1.</p>													
				<p>KEY</p> <ul style="list-style-type: none">1 ODOR CONTROL2 LIFT STATION3 FLEET VEHICLES4 MAINTENANCE BUILDING5 EXISTING DEWATERING6 2.5 MG PEAK FLOW STORAGE7 HEADWORKS8 ODOR CONTROL9 MBR10 MBR SUPPORT BUILDING11 CHEMICAL STORAGE12 EXISTING TOWER13 ASHT14 FUEL FACILITY15 UV/NPW16 ADMINISTRATION BUILDING17 DETENTION POND18 RAS/WAS PUMP STATION19 BLOWER BUILDING20 FUTURE EQ TANK21 FUTURE ADVANCED TREATMENT									
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		Completed	<input type="checkbox"/> CSP	<input type="checkbox"/> O&M									
PSA/WO Issued:		Completed	<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS									
Final Proposal Docs:		TBD	<input checked="" type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R									
Proposals/Bids Received:		TBD	<input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		TBD		<input type="checkbox"/> OTHER									
Substantial Completion:		TBD											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Owner's Advisor**	\$ 14,996,096	\$ 834,096	\$ 1,810,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,162,000	\$ -	\$ -	\$ -	
Total	\$ 14,996,096	\$ 834,096	\$ 1,810,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,038,000	\$ 2,162,000	\$ -	\$ -	\$ -	

*Budget includes 30% contingency, and 3% inflation per year.



** Total Bond Funded portion = \$14,162,000. Total R&R Funded Portion = \$834,096.

PROJECT NAME				PROJECT ID	FISCAL YEAR	DIVISION							
Water Reclamation Facility No. 1				WWF1NP	2023-TBD	The Woodlands							
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>The existing wastewater infrastructure in The Woodlands is aging with certain treatment and conveyance components expected to reach the end of their useful life in the coming decade. Improvements must be made, and actions must be taken to maintain the level of service (LoS) expected by San Jacinto River Authority (SJRA) customers. In March 2023, SJRA completed the initial phase of The Woodlands Wastewater Strategic Plan, which laid out a phased approach to maintaining the desired level of service in The Woodlands. The report also defined a project to replace the aging infrastructure of Wastewater Treatment Facility (WWTF) No. 1. In January 2024, SJRA completed a Facility Master Plan for a new Water Reclamation Facility (WRF) to be located at and adjacent to the existing WWTF No. 1. The current proposed average annual daily flow capacity for the new facility is 7.0 million gallons per day (MGD) with a wet weather peak flow of 18 MGD. The facility master plan was based around a Membrane Bioreactor (MBR) treatment process.</p> <p>An additional study is currently being completed under a separate project (WWF1OA) to compare additional short-listed alternatives for renewal/replacement of WWTF No. 1. SJRA will continue to coordinate with the MUD Boards to determine the best valued renewal/replacement alternative for WWTF No. 1 to move forward with.</p> <p>The required funding shown below is based on project estimates developed during the Facility Master Plan and will be adjusted pending outcome of the additional WWTF No. 1 study. Due to the size and complexity of this project SJRA is considering the use of other alternative delivery methods such as construction manager at risk or progressive design build. Land acquisition may be required in order to construct the new facility.</p>													
				<div><div>KEY</div><div><div>1</div><div>ODOR CONTROL</div></div><div><div>2</div><div>LIFT STATION</div></div><div><div>3</div><div>FLEET VEHICLES</div></div><div><div>4</div><div>MAINTENANCE BUILDING</div></div><div><div>5</div><div>EXISTING DEWATERING</div></div><div><div>6</div><div>2.5 MG PEAK FLOW STORAGE</div></div><div><div>7</div><div>HEADWORKS</div></div><div><div>8</div><div>ODOR CONTROL</div></div><div><div>9</div><div>MBR</div></div><div><div>10</div><div>MBR SUPPORT BUILDING</div></div><div><div>11</div><div>CHEMICAL STORAGE</div></div><div><div>12</div><div>EXISTING TOWER</div></div><div><div>13</div><div>ASHT</div></div><div><div>14</div><div>FUEL FACILITY</div></div><div><div>15</div><div>UV/NPW</div></div><div><div>16</div><div>ADMINISTRATION BUILDING</div></div><div><div>17</div><div>DETENTION POND</div></div><div><div>18</div><div>RAS/WAS PUMP STATION</div></div><div><div>19</div><div>BLOWER BUILDING</div></div><div><div>20</div><div>FUTURE EQ TANK</div></div><div><div>21</div><div>FUTURE ADVANCED TREATMENT</div></div></div>									
				10/9/23									
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		FY 2025 - Q2		<input type="checkbox"/> CSP	<input checked="" type="checkbox"/> O&M								
PSA/WO Issued:		FY 2025 - Q3		<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS								
Final Proposal Docs:		TBD		<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R								
Proposals/Bids Received:		TBD		<input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		TBD			<input type="checkbox"/> OTHER								
Substantial Completion:		TBD											
BUDGET***	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER*	\$ 10,311,194	\$ 1,829,194	\$ 4,620,000	\$ 3,862,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 14,391,000	\$ -	\$ -	\$ 10,413,000	\$ 3,978,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 233,595,000	\$ -	\$ -	\$ -	\$ 46,719,000	\$ 46,719,000	\$ 46,719,000	\$ 46,719,000	\$ 46,719,000	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 22,291,000	\$ -	\$ -	\$ -	\$ 4,672,000	\$ 4,536,000	\$ 4,404,000	\$ 4,275,000	\$ 4,404,000	\$ -	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Owner's Advisor**	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 280,588,194	\$ 1,829,194	\$ 4,620,000	\$ 14,275,000	\$ 55,369,000	\$ 51,255,000	\$ 51,123,000	\$ 50,994,000	\$ 51,123,000	\$ -	\$ -	\$ -	

***Budget includes 30% contingency, and 3% inflation per year.



* Previous effort shown from past related projects - Wastewater Strategic Plan. Total Bond Funded Portion = \$1,787,286. Total O&M Funded Portion = \$41,908.

** Refer to WWF1OA for Owner's Advisor related services.

PROJECT NAME				PROJECT ID	FISCAL YEAR	DIVISION							
WWTF No. 2 Tertiary Filter Improvements (2nd and 3rd Filter)				WW02FR	2021-2027	The Woodlands							
PROJECT DESCRIPTION					PROJECT MAP/PICTURE								
<p>Wastewater Treatment Facility (WWTF) No. 2 utilizes tertiary filters to treat effluent prior to disinfection. Filters 1 and 2 are sand filters, while Filter 3 was replaced with a new cloth media filter in 2016. The current sand filters are rated for 2 MG of flow each, with the one installed cloth media filter rated for 6 MG of flow. The TCEQ discharge permit allows for 15.6 MG of flow during a rain event, of which only 10.0 MG is able to be treated with the current filters.</p> <p>Existing sand filters 1 and 2 have been in service since 2006, have a service life of 15-25 years, are rated for 2 MG each, and have experienced performance issues which limit wastewater flows through WWTF No. 2. This project will replace the remaining two sand filters with cloth media filters which will eliminate the performance issues and allow all flow during a rain event to pass through the filters.</p> <p>An evaluation was conducted in 2021 to determine the capital and O&M cost of replacing the existing unit with a similar unit versus a modification to a newer technology (cloth media). To replace the existing unit with a similar unit, capital and O&M costs were \$106.85/MG and \$27.40, respectively. The capital and O&M cost to modify to cloth media is \$41.76/MG and \$7.99/MG, respectively.</p> <p>Costs are based on an design that was done in 2021 and updated recently with a current engineer's estimate (December 2024). Construction will be funded from 2017 TWDB Wastewater Bonds, whereas the remaining engineering, CMT, etc. will be paid from R&R funds.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:	Completed	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M										
PSA/WO Issued:	Completed	<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS										
Final Proposal Docs:	Completed	<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R										
Proposals/Bids Received:	Completed	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS										
Constr. Contract to Board:	FY 2025 - Q3		<input type="checkbox"/> OTHER										
Substantial Completion:	FY 2027 - Q1												
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER*	\$ 100,000	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design**	\$ 276,118	\$ 276,118	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 5,366,000	\$ 500,000	\$ 4,492,000	\$ 374,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT**	\$ 159,209	\$ 59,209	\$ 92,000	\$ 8,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Land Acquisition	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 5,901,327	\$ 935,327	\$ 4,584,000	\$ 382,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	

*Budget includes 0% contingency, and 0% inflation per year.


**Total Bond Funded Portion = \$5,366,000. Total R&R Funded Portion = \$535,327.

PROJECT NAME				PROJECT ID		FISCAL YEAR		DIVISION				
Wastewater Conveyance Optimization				WWWWCO		2023-2030		The Woodlands				
PROJECT DESCRIPTION				PROJECT MAP/PICTURE								
<p>The large diameter force main associated with Lift Station No. 5 (LS No. 5) was scheduled for replacement in 2024, due to a deteriorated pipe condition which resulted in numerous leaks requiring repair. However through recent Wastewater Strategic Planning efforts, an opportunity was identified to abandon LS No. 5 and replace the force main with a large diameter gravity main. This would also provide an opportunity to abandon other smaller lift stations north of WWTF No. 1 and replace their force mains with gravity lines adjoining the new large diameter gravity main. By eliminating lift stations, a point of potential mechanical or electrical failure, noise, and odor will be reduced in the overall conveyance system. Additionally by eliminating lift stations and their associated force mains, long-term cost savings are anticipated through reduced operations and maintenance costs and elimination of aging and deteriorated infrastructure.</p> <p>In 2023 the Woodlands Board of Trustees approved a route study and design of the project, and the Texas Water Development Board approved the use of the current 2017 Bond funds for the study and design phases. The current route study is evaluating feasibility of a large diameter gravity main between LS No. 5 and WWTF No. 1, abandoning several lift stations in the WWTF No. 1 service area (LS Nos. 2, 3, 18 and 19), and constructing smaller diameter gravity sewer lines to divert flow from these lift stations. This study identified, and is evaluating, potential routes to construct the gravity sewers, identify obstructions, land requirements, methods to eliminate lift stations, and ensure uninterrupted flow to WWTF No. 1. The study also includes a life cycle cost (cost/benefit) analysis for the project. Construction phasing will be critical for optimal completion of the project to ensure uninterrupted wastewater service, and to minimize conflicts with existing utilities, traffic routes, neighborhood activities, and country club/golf course activities.</p>												
PROJECT SCHEDULE				DELIVERY	FUNDING							
Initiate Cons. Selection:		Completed	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		Completed	<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS								
Final Proposal Docs:		FY 2027	<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R								
Proposals/Bids Received:		FY 2027	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		FY 2027		<input type="checkbox"/> OTHER								
Substantial Completion:		FY 2030										
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035
Planning/Permitting/PER	\$ 1,693,749	\$ 747,749	\$ 946,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Engineering/Design	\$ 2,306,251	\$ -	\$ -	\$ 2,306,251	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction	\$ 37,388,749	\$ -	\$ -	\$ 3,124,749	\$ 11,989,000	\$ 12,469,000	\$ 9,806,000	\$ -	\$ -	\$ -	\$ -	\$ -
CPS, CM&I, and CMT	\$ 3,739,000	\$ -	\$ -	\$ 312,000	\$ 1,199,000	\$ 1,247,000	\$ 981,000	\$ -	\$ -	\$ -	\$ -	\$ -
Property Cost**	\$ 250,000	\$ -	\$ -	\$ 250,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Land Acquisition Team**	\$ 250,000	\$ -	\$ -	\$ 250,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total***	\$ 45,627,749	\$ 747,749	\$ 946,000	\$ 6,243,000	\$ 13,188,000	\$ 13,716,000	\$ 10,787,000	\$ -	\$ -	\$ -	\$ -	\$ -

*Budget includes 30% contingency, and 4% inflation per year.


** Budget for Property Cost and Land Acquisition Team to be further defined during the Engineering/Design phase of the project.

*** Of this total, \$4,000,000 is anticipated from 2017 Bonds, and \$45,127,749 will be from new bonds.

PROJECT NAME				PROJECT ID		FISCAL YEAR			DIVISION					
South Shore Gravity Main Rehabilitation				WW21GR		2021-2027			The Woodlands					
PROJECT DESCRIPTION						PROJECT MAP/PICTURE								
<p>Some wastewater lines within the collection system have been in service for over 40 years. The aging system requires rehabilitation to avoid collection system failure, sewage overflows, and permit violations. Through the Asset Management Program and the Sanitary Sewer Transmission Assessment and Renewal (SSTAR) Program, specific line segments were identified as high risk for failure and should be replaced or rehabilitated in the near term.</p> <p>The SSTAR Program conducted in 2019 and 2020 included a condition assessment consisting of closed circuit television (CCTV) inspection and analysis of expected remaining useful life. CCTV video footage showed significant deterioration of the existing gravity mains, requiring rehabilitation or replacement. Additionally, these line segments were scored with a high consequence of failure, due to their location, difficulties with access, and their criticality.</p> <p>This project proposes to renew approximately 9,800 linear feet of existing sanitary sewer gravity mains varying in size from 15-inch to 42-inch, by the cured-in-place pipe (CIPP) pipe lining method, as well as television inspection, bypass pumping to maintain sewer flows during construction, rehabilitation of manholes along the sanitary sewer alignment, service reconnections by remote, and mechanical cleaning if needed.</p> <p>Active communication with the residents of the affected west lake area, as well as the golf course, to coordinate and schedule the necessary work and routing of bypass pump piping is ongoing.</p> <p>Rehabilitation costs are from updated costs from February 2025.</p>														
PROJECT SCHEDULE				DELIVERY	FUNDING									
Initiate Cons. Selection:	Completed	<input checked="" type="checkbox"/>	CSP	<input type="checkbox"/>	O&M									
PSA/WO Issued:	Completed	<input type="checkbox"/>	QUOTES	<input checked="" type="checkbox"/>	BONDS									
Final Proposal Docs:	FY 2025 - Q3	<input type="checkbox"/>	PROFESSIONAL	<input checked="" type="checkbox"/>	R&R									
Proposals/Bids Received:	FY 2025 - Q4	<input type="checkbox"/>	OTHER	<input type="checkbox"/>	GRANTS									
Constr. Contract to Board:	FY 2026 - Q1					<input type="checkbox"/>	OTHER							
Substantial Completion:	FY 2027 - Q3													
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035		
Planning/Permitting/PER	\$ 213,888	\$ 213,888	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Engineering/Design	\$ 640,433	\$ 640,433	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Construction	\$ 10,955,000	\$ -	\$ 7,231,000	\$ 3,724,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
CPS, CM&I, and CMT	\$ 1,095,000	\$ -	\$ 723,000	\$ 372,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Property Cost	\$ 5,000	\$ 5,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Land Acquisition Team	\$ 45,000	\$ 45,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Total**	\$ 12,954,321	\$ 904,321	\$ 7,954,000	\$ 4,096,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		


*Budget includes 30% contingency, and 3% inflation per year.

**\$263,888 is R&R Funds; \$12,690,433 is 2017 Bond Funds


PROJECT NAME				PROJECT ID		FISCAL YEAR		DIVISION					
Lift Station No. 1 Gravity Main Bypass and Decommissioning				WWLS1B		2023-2026		The Woodlands					
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>Lift Station No. 1 was constructed in 1974 to receive wastewater flows from areas along Grogan's Mill Road north of Woodlands Parkway and pump these flows to Wastewater Treatment Facility No. 1. Recent evaluation of the force main, also constructed in 1974, found it to be in poor condition, and in need of replacement. In the mid-1990s, a 42-inch gravity line was constructed approximately 1,400 LF to the west of the lift station, which a feasibility study performed in 2023 found to be at a depth and adequate size to intercept the flows going to Lift Station No. 1. Constructing a gravity main along the north side of Woodlands Parkway from just upstream of the lift station to the 42-inch gravity main would allow the lift station to be cut below grade, gutted and filled and the force main grout-filled and capped, and therefore, eliminate further lift station life cycle operation and maintenance costs for 50-year old infrastructure. The existing 18-inch gravity line receiving flow from Lift Station No. 1's force main will also need to be decommissioned and abandoned.</p> <p>A feasibility study and preliminary engineering have been completed on this project, and final design is underway. The budget costs were derived from the preliminary engineering phase by the design consultant. Final detailed engineering design is currently in progress and the construction cost shown below is an estimate based on assumptions made by the consultant during preliminary engineering with a general understanding of the area. The construction of this project will be funded utilizing bond funds received from the Texas Water Development Board.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		Completed		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		Completed		<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS								
Final Proposal Docs:		FY 2025 - Q3		<input type="checkbox"/> PROFESSIONAL	<input checked="" type="checkbox"/> R&R								
Proposals/Bids Received:		FY 2025 - Q4		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		FY 2026 - Q1			<input type="checkbox"/> OTHER								
Substantial Completion:		FY 2026 - Q4											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 23,711	\$ 23,711	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 194,000	\$ 184,000	\$ 10,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 4,000,000	\$ -	\$ 4,000,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 150,000	\$ -	\$ 150,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Land Acquisition	\$ 20,000	\$ -	\$ 20,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 4,387,711	\$ 207,711	\$ 4,180,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	

*Budget includes 30% contingency, and 3% inflation per year.


**Total Bond Funded portion = \$4,000,000. Total R&R Funded Portion = \$387,711

PROJECT NAME				PROJECT ID	FISCAL YEAR	DIVISION								
Gravity Main Rehabilitation - Hughes Landing and East Shore				WW23GR	2027-2029	The Woodlands								
PROJECT DESCRIPTION				PROJECT MAP/PICTURE										
<p>Some wastewater lines within the collection system have been in service for over 40 years. The aging system requires rehabilitation to avoid collection system failure, sewage overflows, and permit violations. Through the Asset Management Program and the Sanitary Sewer Transmission Assessment and Renewal (SSTAR) Program, specific line segments were identified as high risk for failure and should be rehabilitated within the next few years.</p> <p>The SSTAR Program conducted in 2019 and 2020 included a condition assessment consisting of closed circuit television (CCTV) inspection and analysis of expected remaining useful life. CCTV video footage showed significant deterioration of the existing gravity main, including corrosion at the water-line, eroded joints allowing infiltration, and significant cracking and delamination of the internal liner, both above and below the water-line, allowing for corrosion of ductile iron underneath. Due to the significant service are this line serves, as well as its proximity to The Woodlands Waterway and Lake Woodlands, this line is considered high in criticality.</p> <p>The line segments included in this project include approximately 5,000 linear feet of 42" ductile iron (DI) pipe located east of Lake Woodlands. These segments were installed in 2000-2001.</p> <p>The cost is based upon results from the SSTAR Program with inflation added to the proposed years to design and construct. In FY2025 an additional condition analysis utilizing CCTV data will be conducted to determine if priority and timing of this project needs to be adjusted.</p>														
				PROJECT SCHEDULE				DELIVERY	FUNDING					
				Initiate Cons. Selection:		FY 2027		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M					
PSA/WO Issued:		FY 2027		<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS									
Final Proposal Docs:		FY 2027		<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R									
Proposals/Bids Received:		FY 2028		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS									
Constr. Contract to Board:		FY 2028			<input type="checkbox"/> OTHER									
Substantial Completion:		FY 2029												
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035		
Planning/Permitting/PER	\$ 668,000	\$ -	\$ -	\$ 668,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Engineering/Design	\$ 683,000	\$ -	\$ -	\$ 167,000	\$ 516,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Construction	\$ 7,032,000	\$ -	\$ -	\$ -	\$ 1,719,000	\$ 5,313,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
CPS, CM&I, and CMT	\$ 703,000	\$ -	\$ -	\$ -	\$ 172,000	\$ 531,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Land Acquisition	\$ 513,000	\$ -	\$ -	\$ 220,000	\$ 293,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
Total	\$ 9,599,000	\$ -	\$ -	\$ 1,055,000	\$ 2,700,000	\$ 5,844,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		

*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID	FISCAL YEAR	DIVISION							
Gravity Main Rehabilitation - North Bear Branch				WW25GR	2028-2030	The Woodlands							
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>Some wastewater lines within the collection system have been in service for over 40 years. The aging system requires rehabilitation to avoid collection system failure, sewage overflows, and permit violations. Through the Asset Management Program and the Sanitary Sewer Transmission Assessment and Renewal (SSTAR) Program, specific line segments were identified as high risk for failure and should be rehabilitated within the next few years.</p> <p>The SSTAR Program conducted in 2019 and 2020 included a condition assessment consisting of closed circuit television (CCTV) inspection and analysis of expected remaining useful life. CCTV video footage showed significant deterioration of the existing gravity main, including corrosion at the water-line, eroded joints allowing infiltration, vegetative growth entering the pipe, and erosion of the internal liner, which left untreated, could eventually wear to the ductile iron, resulting in more corrosion. Due to environmental sensitivity of this location adjacent to Bear Branch Reservoir and nearby wetland areas, this line is considered high in criticality.</p> <p>The line segments included in this project include approximately 1,400 linear feet of 18" ductile iron (DI) pipe, 3300 linear feet of 21" DI pipe, and 2100 linear feet of 24" DI pipe. These segments were installed in 1997.</p> <p>The cost is based upon results from the SSTAR Program with inflation added to the proposed years to design and construct. In FY2025 an additional condition analysis utilizing CCTV data will be conducted to determine if priority and timing of this project needs to be adjusted.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		FY 2028		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		FY 2028		<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS								
Final Proposal Docs:		FY 2029		<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R								
Proposals/Bids Received:		FY 2029		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		FY 2029			<input type="checkbox"/> OTHER								
Substantial Completion:		FY 2030											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 457,000	\$ -	\$ -	\$ -	\$ 457,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Engineering/Design	\$ 467,000	\$ -	\$ -	\$ -	\$ 114,000	\$ 353,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Construction	\$ 4,810,000	\$ -	\$ -	\$ -	\$ -	\$ 1,176,000	\$ 3,634,000	\$ -	\$ -	\$ -	\$ -	\$ -	
CPS, CM&I, and CMT	\$ 481,000	\$ -	\$ -	\$ -	\$ -	\$ 118,000	\$ 363,000	\$ -	\$ -	\$ -	\$ -	\$ -	
Land Acquisition	\$ 528,000	\$ -	\$ -	\$ -	\$ 227,000	\$ 301,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 6,743,000	\$ -	\$ -	\$ -	\$ 798,000	\$ 1,948,000	\$ 3,997,000	\$ -	\$ -	\$ -	\$ -	\$ -	


*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID	FISCAL YEAR	DIVISION						
Gravity Main Rehabilitation - Upper Panther Branch				WW27GR	2030-2032	The Woodlands						
PROJECT DESCRIPTION				PROJECT MAP/PICTURE								
<p>Some wastewater lines within the collection system have been in service for over 40 years. The aging system requires rehabilitation or renewal to avoid collection system failure, sewage overflows, and permit violations. Through the Asset Management Program, specific line segments were identified as high risk for failure and should be rehabilitated within the next few years.</p> <p>The SSTAR Program conducted in 2019 and 2020 included assessment of the expected remaining useful life for collection system assets. The fiberglass reinforced plastic (FRP) pipe is showing signs of extensive wear from flow and offgassing from the wastewater. Continued wear without remediation could eventually lead to the pipe being structurally compromised. Due to environmental sensitivity of this location adjacent to Upper Panther Branch and nearby wetland areas, this line is considered high in criticality.</p> <p>The line segments included in this project include approximately 4,300 linear feet of 30" FRP pipe located north of Research Forest Drive, near Wastewater Treatment Facility No. 2.</p> <p>The cost is based upon results from the SSTAR Program with inflation added to the proposed years to design and construct. In FY2025 an additional condition analysis utilizing CCTV data will be conducted to determine if priority and timing of this project needs to be adjusted.</p>												
PROJECT SCHEDULE				DELIVERY	FUNDING							
Initiate Cons. Selection:		FY 2029		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M							
PSA/WO Issued:		FY 2030		<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS							
Final Proposal Docs:		FY 2031		<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R							
Proposals/Bids Received:		FY 2031		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS							
Constr. Contract to Board:		FY 2031			<input type="checkbox"/> OTHER							
Substantial Completion:		FY 2032										
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035
Planning/Permitting/PER	\$ 811,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 811,000	\$ -	\$ -	\$ -	\$ -	\$ -
Engineering/Design	\$ 829,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 203,000	\$ 626,000	\$ -	\$ -	\$ -	\$ -
Construction	\$ 8,540,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,088,000	\$ 6,452,000	\$ -	\$ -	\$ -
CPS, CM&I, and CMT	\$ 854,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 209,000	\$ 645,000	\$ -	\$ -	\$ -
Land Acquisition	\$ 522,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 202,000	\$ 320,000	\$ -	\$ -	\$ -	\$ -
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total	\$ 11,556,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,216,000	\$ 3,243,000	\$ 7,097,000	\$ -	\$ -	\$ -

*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR		DIVISION					
Gravity Main Rehabilitation - West of Lake Woodlands				WW31GR		2032-2034		The Woodlands					
PROJECT DESCRIPTION				PROJECT MAP/PICTURE									
<p>Some wastewater lines within the collection system have been in service for over 40 years. The aging system requires rehabilitation or renewal to avoid collection system failure, sewage overflows, and permit violations. Through the Asset Management Program, specific line segments were identified as high risk for failure and should be rehabilitated within the next few years.</p> <p>The SSTAR Program conducted in 2019 and 2020 included a condition assessment consisting of closed circuit television (CCTV) inspection and analysis of expected remaining useful life. CCTV video footage showed deterioration of the existing gravity main, including corrosion at the water-line, eroded joints allowing infiltration, and erosion of the internal liner, which over time would expose the ductile iron, leading to more extensive corrosion. Due to the significant service are this line serves, as well as its proximity to Lake Woodlands, this line is considered high in criticality.</p> <p>The line segments included in this project include approximately rehabilitation of 150 LF of 21-inch vitrified clay pipe (VCP) and 3,200 LF of 24-inch ductile iron (DI) pipe, and installation of 2,867 LF of 24-inch sanitary sewer line and abandonment of 1,475 LF of 24-inch DI pipe.</p> <p>The cost is based upon results from the SSTAR Program with inflation added to the proposed years to design and construct. In FY2025 an additional condition analysis utilizing CCTV data will be conducted to determine if priority and timing of this project needs to be adjusted.</p>				<div><div><div>Legend</div><div><div><div></div><div>21" (CIPP)</div></div><div><div></div><div>24" (CIPP)</div></div><div><div></div><div>24" Trenchless</div></div><div><div></div><div>24" Open Cut</div></div><div><div></div><div>24" Abandon</div></div></div></div><div></div></div>									
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:		FY 2031		<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M								
PSA/WO Issued:		FY 2032		<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS								
Final Proposal Docs:		FY 2033		<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R								
Proposals/Bids Received:		FY 2033		<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS								
Constr. Contract to Board:		FY 2033			<input type="checkbox"/> OTHER								
Substantial Completion:		FY 2034											
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 782,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 782,000	\$ -	\$ -	\$ -	
Engineering/Design	\$ 799,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 195,000	\$ 604,000	\$ -	\$ -	
Construction	\$ 8,234,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,013,000	\$ 6,221,000	\$ -	
CPS, CM&I, and CMT	\$ 823,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 201,000	\$ 622,000	\$ -	
Land Acquisition	\$ 570,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 231,000	\$ 339,000	\$ -	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 11,208,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,208,000	\$ 3,157,000	\$ 6,843,000	\$ -	

*Budget includes 30% contingency, and 3% inflation per year.

PROJECT NAME				PROJECT ID		FISCAL YEAR				DIVISION			
Gravity Main Rehabilitation - East of Lake Woodlands				WW32GR		2033-2035				The Woodlands			
PROJECT DESCRIPTION						PROJECT MAP/PICTURE							
<p>Some wastewater lines within the collection system have been in service for over 40 years. The aging system requires rehabilitation or renewal to avoid collection system failure, sewage overflows, and permit violations. Through the Asset Management Program, specific line segments were identified as high risk for failure and should be rehabilitated within the next few years.</p> <p>The SSTAR Program conducted in 2019 and 2020 included a condition assessment consisting of closed circuit television (CCTV) inspection and analysis of expected remaining useful life. CCTV video footage showed significant deterioration of the existing gravity main, including corrosion at the water-line, eroded joints allowing infiltration, and cracking and delamination of the internal liner near the joints, both above and below the water-line, allowing for corrosion of ductile iron underneath. Due to the significant service are this line serves, as well as its proximity to Lake Woodlands, this line is considered high in criticality.</p> <p>The line segments included in this project include rehabilitation of approximately 3,575 LF of 42-inch ductile iron (DI) gravity main.</p> <p>The cost is based upon results from the SSTAR Program with inflation added to the proposed years to design and construct. In FY2025 an additional condition analysis utilizing CCTV data will be conducted to determine if priority and timing of this project needs to be adjusted.</p>													
PROJECT SCHEDULE				DELIVERY	FUNDING								
Initiate Cons. Selection:				FY 2032	<input checked="" type="checkbox"/> CSP	<input type="checkbox"/> O&M							
PSA/WO Issued:				FY 2033	<input type="checkbox"/> QUOTES	<input checked="" type="checkbox"/> BONDS							
Final Proposal Docs:				FY 2034	<input type="checkbox"/> PROFESSIONAL	<input type="checkbox"/> R&R							
Proposals/Bids Received:				FY 2034	<input type="checkbox"/> OTHER	<input type="checkbox"/> GRANTS							
Constr. Contract to Board:				FY 2034		<input type="checkbox"/> OTHER							
Substantial Completion:				FY 2035									
BUDGET*	TOTAL	PREVIOUS	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	
Planning/Permitting/PER	\$ 538,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 538,000	\$ -	\$ -	
Engineering/Design	\$ 551,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 135,000	\$ 416,000	\$ -	
Construction	\$ 5,667,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,386,000	\$ 4,281,000	
CPS, CM&I, and CMT	\$ 567,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 139,000	\$ 428,000	
Land Acquisition	\$ 570,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 221,000	\$ 349,000	\$ -	
Equipment Purchase	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
Total	\$ 7,893,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 894,000	\$ 2,290,000	\$ 4,709,000	

*Budget includes 30% contingency, and 3% inflation per year.